

# **SDMS US EPA REGION V -1**

**SOME IMAGES WITHIN THIS  
DOCUMENT MAY BE ILLEGIBLE  
DUE TO BAD SOURCE  
DOCUMENTS.**



U.S. Environmental Protection Agency →

## **Round 1 Long Term Groundwater Monitoring Report**

Spickler Landfill Site  
Spencer, Wisconsin

August 5, 1996



August 5, 1996

United States Environmental Protection Agency  
Region V  
77 West Jackson Blvd.  
Chicago, IL 60604

Attn: Mr. John Fagiolo  
Remedial Project Manager

Re: Round 1 Long Term Groundwater Monitoring Report for the Spickler Landfill Site --  
STS Project No. 84374XA


Dear Mr. Fagiolo:


On behalf of the Settling Defendants for the Spickler Landfill Site in Spencer, Wisconsin, STS Consultants, Ltd. (STS) is submitting the results of Round 1 of the Long Term Groundwater Monitoring. Round 1 of the Long Term Groundwater Monitoring was completed in accordance with the O&M Plan and QAPP. One copy of the complete data set has been provided under separate cover to the U.S. EPA.

As part of the long term monitoring program, wells S1A, S2A and S3A have been replaced at the same depths with S1AR, S2AR and S3AR. One overlapping round of groundwater quality data has been collected in both the older and replacement wells to ensure comparability of data trends as requested. Based on the data collected, we are formally requesting approval to abandon older wells S1A, S2A and S3A, since they are out of compliance with current State well installation regulations.

Respectfully submitted,

STS CONSULTANTS, LTD

  
Jane A. Kettler  
Project Chemist

  
Jeanne M. Tarvin, P.G., CPG  
Principal Hydrogeologist

Attachments

©STS Consultants, Ltd., August 1996

cc: See Distribution List

**STS Consultants Ltd.**  
Consulting Engineers

11425 West Lake Park Drive  
Milwaukee, Wisconsin 53224  
414.359.3030/Fax 414.359.0822



### **DISTRIBUTION LIST**

Mr. Larry Lester - WDNR  
Ms. Jane Lemcke - WDNR  
Mr. Henry Nehls-Lowe - Wisconsin Division of Public Health  
Mr. James P. Odendahl - Weyerhaeuser Company  
Mr. Mark Johnson - Weyerhaeuser Company  
Mr. Dale E. Webster - BASF  
Mr. Christopher Miastros - Bata Shoe Company, Inc.  
Mr. Mark Thimke - Foley & Lardner  
Mr. James P. Lonsdorf - Lonsdorf & Andraski  
Ms. Nancy Peterson - Quarles & Brady  
Ms. Jeanne M. Tarvin - STS Consultants, Ltd.  
Ms. Jane A. Kettler - STS Consultants, Ltd.

*Report*

---

---

**PROJECT**

LONG TERM GROUNDWATER  
MONITORING, ROUND 1  
MARCH, 1996  
SPICKLER LANDFILL SITE

---

**CLIENT**

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION V  
77 WEST JACKSON BOULEVARD  
CHICAGO, IL 60604

---

*Project No.*

84374XA

---

*Date*

AUGUST 5, 1996

---



**STS Consultants, Ltd.**  
Consulting Engineers  
11425 West Lake Park Drive  
Milwaukee, Wisconsin 53224  
414.359.3030/Fax 413.359.0822

## **TABLE OF CONTENTS**

**Page No.**

<b>1.0 INTRODUCTION.....</b>	<b>1</b>
<b>2.0 FIELD SAMPLING PROCEDURES .....</b>	<b>2</b>
2.1 Sample Collection .....	2
2.2 Sample Transportation .....	3
2.3 Field and Laboratory Analytical Procedures.....	3
2.3.1 Field Analyses .....	3
2.3.2 Laboratory Analyses .....	3
<b>3.0 RESULTS OF FIELD AND LABORATORY ANALYTICAL DATA.....</b>	<b>4</b>
3.1 Results of Field Analytical Data .....	4
3.1.1 Monitoring Wells.....	4
3.1.2 Residential Wells .....	4
3.2 Results of Laboratory Analytical Data .....	5
3.2.1 Monitoring Wells.....	5
3.2.2 Residential Wells .....	7
3.3 Conclusions .....	7
3.4 Recommendations .....	9
<b>4.0 QUALITY ASSURANCE REVIEW OF ANALYTICAL DATA .....</b>	<b>10</b>
4.1 Field Data .....	10
4.2 Laboratory Data.....	10
4.2.1 Sample Handling and Analytical Methods .....	10
4.2.2 Blanks .....	11
4.2.3 Surrogate and Matrix Spike Recoveries .....	11
4.2.4 Quality Assurance Summary .....	12

## **FIGURES**

- Figure 1 - Site Location Diagram
- Figure 2 - Long-Term Monitoring Well Location Diagram
- Figure 3 - Groundwater Table Contour Map
- Figure 4 - Piezometric Head Distribution

## **TABLE OF CONTENTS (cont.)**

### **TABLES**

Table 1 - Groundwater Elevation Summary

Table 2A -Field Parameters, Groundwater Monitoring Wells

Table 2B -Field Parameters, Residential Wells

Table 3A -Metal and Cyanide Concentrations, Groundwater Monitoring Wells

Table 3B -Metal and Cyanide Concentrations, Residential Wells

Table 4A -Volatile Organic Compound Concentrations, Groundwater Monitoring Wells

Table 4B -Volatile Organic Compound Concentrations, Residential Wells

Table 5A -Phthalate Concentrations, Groundwater Monitoring Wells

Table 5B -Phthalate Concentrations, Residential Wells

### **APPENDICES**

Appendix A - Field Sampling Sheets

Appendix B - Chain-of-Custody Forms

Appendix C - HES Case Narrative

**LONG TERM GROUNDWATER MONITORING  
ROUND 1  
SPICKLER LANDFILL SITE  
MARCH, 1996**

**1.0 INTRODUCTION**

On behalf of the Settling Defendants, STS Consultants, Ltd. (STS) has completed Round 1 of the Long Term Groundwater Monitoring for the Spickler Landfill Site. The monitoring was completed from March 12, 1996 to March 22, 1996. The Spickler Landfill Site is located in the northwest quarter of the southeast quarter of Section 33, Township 26N, Range 2E, Marathon County, Wisconsin. Figure 1 presents a Site Location Diagram.

The Long Term Groundwater Monitoring (LTGWM) includes sampling and analysis of groundwater monitoring and residential wells. The LTGWM Program is detailed in the final LTGWM Plan dated November 3, 1995. Protocols for sampling, sample handling and storage, sample chain-of-custody, laboratory and field analyses, and data evaluation are specified in the Spickler LTGWM Quality Assurance Project Plan (QAPP) dated November 3, 1995.

The objective of the LTGWM is to monitor groundwater at the landfill and nearby residences in order to evaluate the effectiveness of the remedy and to detect deterioration in groundwater quality. Deterioration, if any, in groundwater quality will be assessed by comparison of the LTGWM results to data collected prior to the remedial action and to action levels specified in the Wisconsin Administrative Code (WAC).

This Technical Memorandum presents the results of Round 1 of the LTGWM. Summary data tables are attached as Tables 1 through 5, and a copy of the complete data package as received from the analytical laboratory has been submitted to the U.S. EPA under separate cover. The analytical laboratory, Hazleton Environmental Services (HES), qualified the data as specified in the analytical methods included in the QAPP. Upon review of the analytical data, STS further qualified some of the data points, including some which appeared to reflect post-sampling contamination. The data qualification procedures were performed in accordance with the "National Functional Guidelines for Organic Data Review" and the "National Functional Guidelines for Inorganic Data Review," both documents dated February 1994.



## **2.0 FIELD SAMPLING PROCEDURES**

### **2.1 Sample Collection**

Groundwater samples were collected in accordance with the LTGWM Plan and QAPP. Samples were collected, preserved, and transported in accordance with the procedures outlined in the QAPP. Copies of the field sampling sheets documenting sample collection and field activities are attached in Appendix A.

The following monitoring and residential wells were sampled:

Monitoring Wells: MW-6S, MW-6D, MW-7S, MW-7D, MW-10S, MW-11S, MW-13S, MW-13D, MW-14S, MW-15S, MW-15D, MW-19S, MW-19D, MW-20S, MW-S1, MW-S1A, MW-S2, MW-S2A, MW-S3, MW-S3A, MW-S1AR, MW-S2AR, MW-S3AR

Residential Wells: RW-2543, RW-2551

Monitoring wells MW-S1AR, MW-S2AR, and MW-S3AR were installed in March 1996 to replace wells MW-S1A, MW-S2A, and MW-S3A which do not conform to the current well construction requirements in NR141, WAC. One overlapping round of data was collected in both the older existing wells and the replacement wells to ensure correlation of long term trends in water quality for these well locations. Upon regulatory agency concurrence, older, existing wells MW-S1A, MW-S2A, and MW-S3A will be abandoned in accordance with NR141, WAC. Installation of MW-S1AR, MW-S2AR, and MW-S3AR was discussed further in correspondence from STS to the U.S. EPA dated February 15, 1996; March 7, 1996; March 15, 1996; and Progress Report No. 32, dated June 7, 1996. Figure 2 presents a diagram of the site layout showing the residences and monitoring well locations.

Prior to sample collection at monitoring well locations, the depth to water was measured in the functioning wells, including those not sampled as part of the LTGWM. Data for depth to groundwater was used to determine the volume of water to be purged from each well and to calculate the groundwater elevation at each well. Field sampling personnel attempted to purge each well of four well volumes, although some wells purged dry. The volume of water purged from each well prior to sampling is included on field sampling sheets in Appendix A.

Data on groundwater elevations were compiled and compared to previously collected data to determine the current hydrogeologic conditions at the site. Groundwater elevations observed over the previous one year period are shown in Table 2. A groundwater contour map is presented as Figure 3, where a piezometric head distribution contour map is presented as Figure 4 for the March 1996 sampling round.

## **2.2 Sample Transportation**

Samples were sent to HES in Madison, Wisconsin for analytical testing in accordance with the QAPP. Samples were placed on ice in coolers as they were collected. Samples were shipped by overnight carrier to HES. Included with the samples were Chain-of-Custody forms which were completed as the samples were collected. Copies of the completed Chain-of-Custody forms are included in Appendix B.

## **2.3 Field and Laboratory Analytical Procedures**

### **2.3.1 Field Analyses**

Groundwater samples were analyzed in the field for the following parameters in accordance with procedures outlined in the QAPP:

- Temperature
- pH
- Conductivity

Measurements were made as soon as possible after sample collection. Measurements of temperature were used to convert conductivity measurements to specific conductance at 25°C. The results of these measurements are included in Tables 1A, 1B and 1C.

### **2.3.2 Laboratory Analyses**

Groundwater samples were analyzed by HES for the following parameters:

- Volatile Organic Compounds (VOCs) (naphthalene plus those VOCs associated with the Superfund Analytical Method for low concentration water).
- Metals (arsenic, barium, chromium, iron, lead, manganese, mercury and cyanide).
- Phthalates (di-n-butyl phthalate, bis-2-ethyl hexyl phthalate, di-ethyl phthalate).

Laboratory analytical procedures are discussed in the QAPP.

### **3.0 RESULTS OF FIELD AND LABORATORY ANALYTICAL DATA**

The results of the field and laboratory analytical data have been compiled into two categories: monitoring wells and residential wells. NR140, Wisconsin Administrative Code (WAC) standards will be used throughout the LTGWM to assess the quality of groundwater sampled from the monitoring wells and residential wells. Groundwater quality trends have been preliminarily evaluated by comparing the December 1993 sampling round to the March 1996 sampling round. A detailed analysis, however, will be performed after an additional round of data is collected. Site specific background water quality data is not available for comparison. Previous attempts by the settling defendants to obtain permission to install upgradient, background wells off-site have been unsuccessful.

#### **3.1 Results of Field Analytical Data**

##### **3.1.1 Monitoring Wells**

The field analytical data collected from the monitoring wells during Round 1 of the LTGWM are presented in Table 2A.

From the December 1993 to the March 1996 sampling round, seven wells had changes in pH which were greater than 0.5 units. At five of the seven wells, pH increased toward a more neutral pH. Well MW-13D had a pH increase of 1.2 units. Wells MW-11S and MW-S2A had decreases in pH. During the interim monitoring, pH at these and other wells had typically varied by less than 0.5 units from one sampling round to the next.

Changes of greater than 20% in conductivity were observed at 10 wells. In the cases of wells MW-6D, MW-7D, MW-13D, and MW-15D the change may be due to errors in recording the conductivity values in December, 1993 since the December 1993 readings were approximately one tenth of the September 1993 and March 1996 readings. Conductivity in the other 6 wells (MW-11S, MW-19S, MW-S1, MW-S2, MW-S2A, and MW-S3) has decreased over the course of the last 3 sampling rounds. Conductivity is generally proportional to total dissolved solids content.

##### **3.1.2 Residential Wells**

Results of the field analyses of residential well samples are presented in Table 2B. The March 1996 pH value at RW-2543 was 0.6 units lower than that observed in December 1993, whereas, the conductivity value was 24% lower than that observed in December, 1993. March 1996 pH and conductivity at RW-2551 were consistent with the December 1993 data.

### **3.2 Results of Laboratory Analytical Data**

Laboratory analyses were performed for metals and cyanide, VOCs and three phthalates. Results for inorganics are presented on Tables 3A and 3B. Results for VOCs are presented on Tables 4A, and 4B. Results for phthalates are presented on Tables 5A and 5B. The first columns of each table present the NR140 WAC Enforcement Standards (ESs), NR140, WAC Preventive Action Limits (PALs), method detection limits and reporting limits for each compound.

The analytical results have been qualified by HES and/or STS. Definitions for the data qualifiers used are listed at the foot of each table. The laboratory analytical results observed for monitoring wells and residential wells are discussed below.

#### **3.2.1 Monitoring Wells**

Analytical results for monitoring wells are presented in Tables 3A, 4A, and 5A.

VOCs - The results of analysis of the monitoring well samples show nine ES exceedances and 21 PAL exceedances. ES and PAL exceedances for VOCs in samples from monitoring wells were as follows:

##### **ES Exceedances**

<b><u>Parameters</u></b>	<b><u>Sample ID</u></b>
Vinyl Chloride	MW-6S, MW-10S, MW-13S, MW-S1A, MW-S1AR MW-S2A, MW-S3, MW-S3A, MW-S3AR

(Additional ES exceedances were observed for methylene chloride in a field blank and a trip blank.)

##### **PAL Exceedances**

<b><u>Parameters</u></b>	<b><u>Sample ID</u></b>
1,2-dichloroethane	MW-6S, MW-S3A, MW-S3AR
Benzene	MW-6S, MW-10S, MW-11S, MW-13S, MW-20S, MW-S1A, MW-S1AR, MW-S2A MW-S3, MW-S3A, MW-S3AR
Chloroform	MW-S1AR
Cis-1,2-dichloroethene	MW-S1AR
Trichloroethene	MW-6S, MW-S1AR, MW-S1A
Vinyl chloride	MW-20S
Bromodichloromethane	MW-S3AR

(Additional PAL exceedances were observed for chloromethane in 2 trip blanks and 1 field blank; and methylene chloride in one trip blank, 4 method blanks, and 2 storage blanks.)

The March 1996 data differ from the Interim Monitoring data (collected prior to the remedy construction) in that March 1996 total xylene, ethylbenzene, and toluene concentrations were lower in several of the samples. The most significant decreases were for xylene in samples MW-6S, MW-13S, MW-S2, MW-S2A, and MW-S3. Total xylene concentrations in MW-13S, MW-S2, MW-S2A, and MW-S3 ranged from 270 to 770  $\mu\text{g/L}$  in December 1993 but ranged from only 6 to 100  $\mu\text{g/L}$  in March 1996.

More vinyl chloride NR140 exceedances were observed in March 1996 than in December 1993, including ES exceedances for vinyl chloride in samples from MW-13S and MW-S2A, and a PAL exceedance for vinyl chloride in sample MW-20S. But since the March 1996 vinyl chloride concentrations were less than 1 they were not, therefore, significantly different from the December 1993 concentrations for the same wells which were reported as not detected above the contract required quantitation limit (CRQL) of 1.

Metals - ES exceedances for iron and manganese were observed for samples MW-6S, MW-10S, MW-11S, MW-13S, MW-19S, MW-S1A, MW-S1AR, MW-S2, MW-S2A, MW-S3, and MW-S3AR. ES exceedances for manganese only were observed for MW-19D and MW-S3A. PAL exceedances for metals were as follows:

<u>Parameters</u>	<u>Sample ID</u>
Arsenic	MW-15S
Barium	MW-11S, MW-13S, MW-S1AR, MW-S2
Iron	MW-7D

No PAL or ES exceedances were observed for cyanide. Cyanide was detected in several samples, but the levels were comparable to what was detected in a field blank so the sample concentrations were qualified with a "u". The highest cyanide concentration detected was approximately 10 times less than the PAL of 40  $\mu\text{g/L}$ .

With the exception of iron concentrations in MW-S2 and MW-S2A, March 1996 metal concentrations were similar to the metal concentration observed prior to the remedial construction. March 1996 iron concentrations in MW-S2 and MW-S2A were 15% and 5% respectively of the December 1993 iron concentrations for the same wells. The conductivity measurements for these two wells also dropped by 30 to 50%. Both of these wells also showed significant changes in total xylene concentrations.

Since changes in metal concentrations may be attributable to changes in atmospheric pressure and local groundwater infiltration rates, the data will continue to be evaluated for stable trends in metal concentrations.

Cyanide was not detected above the NR140 PAL in any of the LTGWM Round 1 samples. The March 1996 cyanide samples were treated with sulfamic acid to remove potential interferences from other nitrogen compounds. Although cyanide was detected in several of the March 1996 samples, the values were very low and were comparable to those detected in field or method blanks and so the data were qualified with a "u". Similarly many of the cyanide concentrations reported during the Interim Monitoring were qualified with a "u". Reported cyanide values for March 1996 samples were lower than the December 1993 samples in all samples except MW-15S. Since cyanide results were lower in samples treated with sulfamic acid, and cyanide has not been detected above the PAL, we propose dropping cyanide from the list of groundwater monitoring parameters.

### Phthalates

Phthalates were detected in several samples, but were also detected in field and method blanks. In most cases, the phthalate concentrations in samples were comparable to those detected in field or method blanks, so the sample concentrations were qualified with a "u". At this time, groundwater quality standards exist only for bis (2-ethylhexyl) phthalate. The WDNR is planning, however, to evaluate di-n-butyl phthalate and diethyl phthalate for possible inclusion on the NR140 list in 1996 or 1997.

One ES exceedance of bis (2-ethylhexyl) phthalate was observed in sample MW-S3AR and PAL exceedances of bis (2-ethylhexyl) phthalate were observed in four method blanks. Since detection of phthalates has been shown in all recent sampling rounds to be related to post-sampling contamination, we propose dropping phthalates from the list of groundwater monitoring parameters.

### 3.2.2 Residential Wells

The results of the laboratory analyses of the residential well samples are presented in Tables 3B, 4B, and 5B. No PAL or ES exceedances were observed for VOCs, metals, cyanide, or phthalates. Results were comparable to those observed previously.

### 3.3 Conclusions

Round 1 of the LTGWM was conducted 27 months after completion of four quarters of Interim Monitoring conducted from March 1993 to December 1993. During that 27 month period, leachate and gas removal systems were installed within the fill areas, and an engineered cover was placed over the fill areas.

The purpose of the Interim Monitoring was to provide a data base against which post-remedial groundwater data could be compared. One purpose of the LTGWM is to provide post-

remedial data to be used to evaluate the effect of the leachate and gas removal systems on groundwater quality. Since only one round of post-remedial groundwater quality data is available, no conclusions regarding trends or changes in groundwater quality will be made at this time. The results of Round 1 of the LTGWM did, however, differ from the Interim Monitoring data as follows:

- Post-remedial concentrations of xylenes decreased as much as one to two orders of magnitude in samples from MW-13S, MW-S2, MW-S2A, and MW-S3. Each of these wells is downgradient of and within approximately 120 feet of the old fill area.
- Iron concentrations in samples from MW-S2 and MW-S2A decreased by approximately one order of magnitude.
- Specific conductance in samples from MW-11S, MW-19S, MW-S1, MW-S2, MW-S2A, and MW-S3 has decreased over the past three sampling rounds. Each of these wells is within approximately 90 feet of one of the fill areas.

The results of the Round 1 LTGWM were consistent with the Interim Monitoring data in the following respects:

- Phthalates, though detected in many groundwater samples, were also present at approximately the same concentrations in the field and method blanks. As a result, nearly all phthalate data points have been qualified with a "u" meaning "not detected above the concentration shown." Phthalates do not appear to be a site contaminant and continued analysis for phthalates will not provide useful, representative data.
- Cyanide was detected in several samples, as it had been in the Interim Monitoring. Sample concentrations were similar to those seen in field blanks, and were, in accordance with the data validation guidelines, qualified with a "u". The cyanide concentrations were slightly lower than those detected during the Interim Monitoring, possibly due to pre-treatment of samples to remove interferences. Continued analysis for cyanide is not necessary given it does not appear to be a site contaminant.
- Naphthalene was added to the list of target VOCs for a minimum of one round of the LTGWM. Naphthalene was included on the list of target compounds for Round 1 of the Interim Monitoring, but was dropped from the list of compounds for Interim Monitoring Rounds 2,3, and 4 because it was detected in few samples and at very low levels.

The highest concentration of naphthalene detected during Round 1 of the LTGWM was a concentration of 3  $\mu\text{g/L}$  in a method blank. Other method blanks also contained naphthalene, but at lower concentrations. Naphthalene was detected at concentrations of less than 1  $\mu\text{g/L}$  in several samples, but the values were qualified

with a "u" since similar or higher naphthalene levels in method blanks suggested a laboratory-borne contaminant source. Continued monitoring for naphthalene is not necessary since it does not appear to be a site contaminant.

### **3.4 Recommendations**

Based on the observations noted above, STS makes the following recommendations for subsequent rounds of the LTGWM:

- Eliminate testing for phthalates, naphthalene, and cyanide since data acquired to date does not indicate that groundwater has been affected by phthalates, naphthalene, or cyanide.



## **4.0 QUALITY ASSURANCE REVIEW OF ANALYTICAL DATA**

### **4.1 Field Data**

The pH and conductivity meters were calibrated daily. Relative percent error (RPE) was determined by analysis of a check standard after every 10 or fewer samples, and Relative Percent Difference (RPD) was determined by analysis of a duplicate sample with every 10 or fewer samples. RPE for pH standards should be within 0.1 units of the true value and results of duplicate analysis for pH should agree within 0.2 units. The RPE of conductivity standards should be within 10 percent of the true value and the RPD of duplicate analysis of samples for conductivity should be within 15 percent. QA measurements for conductivity consistently fell within the control limits specified above.

QA measurements for pH exceeded the QC limit in one case. On March 12, 1996, the pH RPE for the 7.00 standard taken at the end of the day was 0.16 unit which exceeds the control limit of 0.1 unit. Samples MW-6S, MW-19D, MW-19S, MW-19S (Dupe) and MW-FB01 were analyzed before the QC exceedance and the pH data may, therefore, be suspect. Analysis of check standards throughout the remainder of the sampling event fell within the RPE limit of 0.1 unit. The RPE for duplicate analyses for pH consistently fell within the limit of 0.2 unit.

### **4.2 Laboratory Data**

The analytical work for Round 1 of the LTGWM was completed in accordance with the QAPP. Methods of sample preservation and holding times are specified in the QAPP. Laboratory analytical methods, laboratory QA measurements and acceptance criteria for the QA measurements are specified in the QAPP or the associated Standard Operating Procedures (SOP) cited in the QAPP.

A brief case narrative was submitted by HES which discusses adherence of laboratory procedures and QA measurements to the standards specified in the QAPP. A copy of the HES narrative is provided as Appendix C to this technical memo. The following is a summary of the information presented in the HES narrative along with observations made during the QA evaluation performed by STS.

#### **4.2.1 Sample Handling and Analytical Methods**

The samples were preserved, secured, and analyzed in accordance with the QAPP. Copies of the completed chain-of-custody forms documenting sample collection, identification, preservation, and condition upon receipt are included in Appendix B to this technical memorandum.

The samples for VOCs, metals and cyanide were analyzed within the holding times specified in the QAPP. All SVOC samples except one of two duplicate samples from MW-13S were analyzed within the holding time for SVOCs. Sample MW-13S-Dupe was re-extracted and analyzed outside the holding time due to non-compliant surrogate recovery during the first analysis. Holding times were calculated from the date of sample receipt at the laboratory.

#### 4.2.2 Blanks

Method and storage blanks were analyzed at the frequency specified in the analytical procedures. The storage blanks (used for VOCs only) contained methylene chloride, toluene, xylenes, and naphthalene. Methylene chloride concentrations in both storage blanks exceeded the PAL.

One or more VOC method blanks contained detectable levels of 1,2-dichlorobenzene, 2-hexanone, 4-methyl-2-pentanone, methylene chloride, toluene, xylene, and naphthalene. One or more method blanks for SVOCs contained bis (2-ethyl hexyl) phthalate, di-n-butylphthalate, and di ethyl phthalate. Method blanks for metals contained arsenic, iron, manganese and mercury. Concentrations of target analytes detected in the method blanks were within the control limits specified in the QAPP and in the analytical procedures. Analyte concentrations detected in samples at concentrations less than 5 times the concentrations in method blanks or storage blanks are flagged with a "u" to indicate that the data is likely not representative of site conditions.

Field and trip blanks were prepared at the frequency and according to the procedures specified in the QAPP. The field blanks monitor for contamination introduced during or after the sampling procedure. The trip blanks monitor for contamination introduced to VOC samples during container shipment from the laboratory and sample shipment to the laboratory. Results of field and trip blanks are shown on the attached tables. In accordance with the National Functional Guidelines, analyte concentrations detected in samples at concentrations less than five times those detected in trip or field blanks are flagged with a "u" to indicate that the data is likely not representative of actual site conditions. In accordance with these guidelines, all cyanide values, all but one bis (2-ethyl hexyl) phthalate value, all di-n-butyl phthalate values, and many VOC values have been qualified with a "u".

#### 4.2.3 Surrogate and Matrix Spike Recoveries

Surrogates are added to each of the samples to be analyzed for VOCs to monitor for purging efficiency. Surrogate recoveries for VOCs were within the control limits for each of the samples, method blanks, and matrix spike samples analyzed.

Matrix spiking solutions are added to one of every twenty samples to be analyzed for VOCs or metals to monitor for matrix interference. Matrix spikes for VOCs were prepared in

duplicate. Spike recoveries and reproducibility were evaluated for 1,1-dichloroethene, trichloroethene, benzene, toluene, and chlorobenzene. Both the individual spike recoveries and the relative percent difference (RPD) of the duplicates were calculated and compared to control limits. High (or low) spike recoveries indicate a possible high (or low) bias in the reported values of these and similar compounds detected in the samples. The RPD is a measure of precision or reproducibility. All spiking compounds were recovered within the control limits. The RPD for each of the five spiking compounds and for each VOC MS/MSD pair were within control limits.

Surrogates are not used in the metals analyses and matrix spikes are added only once rather than in duplicate. The matrix spike for metals is added to one of every twenty samples. A matrix spiking solution consisting of arsenic, barium, cadmium, chromium, iron, lead, manganese, mercury, and cyanide was added to three samples. Matrix spike recoveries were within control limits.


In addition to the matrix spikes, post-digestion spikes were used for metals analyzed by graphite furnace methods (arsenic and lead). Post-digestion spike recovery for lead exceeded the upper control limit of 115% for samples MW-10S, and MW-S2. Post-digestion spike recoveries for the remaining samples and parameters were within control limits.

High matrix spike recoveries indicate a possible high bias in the reported results. Lead was not detected above the detection limit of 1  $\mu\text{g/L}$  in either of the two groundwater samples with high spike recovery. The high spike recoveries are not believed, therefore, to significantly affect the data quality.

#### 4.2.4 Quality Assurance Summary


The laboratory analytical data is generally considered to be complete and meets the QA/QC criteria established in the QAPP. An attempt has been made, through application of the Guidelines for Data Validation, to identify non-representative data resulting from post-sampling contamination. The affected sample results have been appropriately qualified. Data which may reflect a bias based upon high or low spike recovery have also been appropriately qualified.

FIGURES



## **LIST OF FIGURES**

- Figure 1 - Site Location Diagram
- Figure 2 - Long-Term Monitoring Well Location Diagram
- Figure 3 - Groundwater Table Contour Map
- Figure 4 - Piezometric Head Distribution



Source: U.S.G.S. TOPOGRAPHIC MAP/MARSHFIELD AND GRANTON QUADRANGLES



STS Consultants, Ltd.

PROJECT/CLIENT

SITE LOCATION MAP  
REMEDIAL DESIGN PROJECT  
SPICKLER LANDFILL  
TOWN OF SPENCER  
MARATHON COUNTY, WISCONSIN

DRAWN BY C.R.H. 10/28/92

CHECKED BY L.K.S. 10/28/92

APPROVED BY T.W.K. 10/28/92

SCALE 1"=5280' FIGURE NO. 1

CADFILE 894-11.R1 STS PROJECT NO.

PLOT DATE 10-28-92 83894XF

# SDMS US EPA REGION V

## FORMAT- OVERSIZED - 5

### IMAGERY INSERT FORM

The item(s) listed below are not available in SDMS. In order to view original document or document pages, contact the Superfund Records Center.

<b>SITE NAME</b>	<b>SPICKLER LANDFILL</b>		
<b>DOC ID #</b>	<b>150820</b>		
<b>DESCRIPTION OF ITEM(S)</b>	<b>OVERSIZE SITE MAPS</b>		
<b>REASON WHY UNSCANNABLE</b>	<u>  X  </u> OVERSIZED	OR	<u>      </u> FORMAT
<b>DATE OF ITEM(S)</b>			
<b>NO. OF ITEMS</b>	<b>2</b>		
<b>PHASE</b>	<b>SAS</b>		
<b>PRP</b>			
<b>PHASE</b> (AR DOCUMENTS ONLY)	<u>      </u> Remedial <u>      </u> Removal <u>      </u> Deletion Docket <u>      </u> AR <u>      </u> Original <u>      </u> Update # <u>      </u> Volume <u>      </u> of <u>      </u>		
<b>O.U.</b>			
<b>LOCATION</b>	<b>Box #</b> <u>      </u> <b>Folder #</b> <u>      </u> <b>Subsection</b> <u>      </u>		
<b>COMMENT(S)</b>			
<b>PARTIAL COPY OF OVERSIZED SITE MAPS</b>			

NOTE:

1. GROUNDWATER ELEVATIONS TAKEN JUNE 13, 1996
2. TOPOGRAPHIC BASE MAP PREPARED FROM AERIAL SURVEY PERFORMED BY KBM, INC. GRAND FORKS, SOUTH DAKOTA FOR WARZYN ENGINEERING INC., FROM PHOTOGRAPHY DATED APRIL 11, 1988. TOPOGRAPHIC BASE MAP OF LANDFILL SHOWS AS-BUILT FINISH GRADES DATED OCTOBER 14, 1994.



STS Consultants Ltd.  
Consulting Engineers

STS PROJECT NUMBER

84374XA

STS DRAWING NUMBER

84374XA-1


SCALE

AS SHOWN

SHEET NUMBER

3

SCALE IN FEET





NOTE:

1. GROUNDWATER ELEVATIONS TAKEN JUNE 13, 1996
2. TOPOGRAPHIC BASE MAP PREPARED FROM AERIAL SURVEY PERFORMED BY KBM, INC. GRAND FORKS, SOUTH DAKOTA FOR WARZYN ENGINEERING INC., FROM PHOTOGRAPHY DATED APRIL 11, 1988. TOPOGRAPHIC BASE MAP OF LANDFILL SHOWS AS-BUILT FINISH GRADES DATED OCTOBER 14, 1994.



STS Consultants Ltd.  
Consulting Engineers

STS PROJECT NUMBER

84374XA

STS DRAWING NUMBER

84374XA-4

SCALE

AS SHOWN

SHEET NUMBER


4

SCALE IN FEET



STS

TABLES



## **LIST OF TABLES**

- Table 1 - Groundwater Elevation Summary
- Table 2A - Field Parameters, Groundwater Monitoring Wells
- Table 2B - Field Parameters, Residential Wells
- Table 3A - Metal and Cyanide Concentrations, Groundwater Monitoring Wells
- Table 3B - Metal and Cyanide Concentrations, Residential Wells
- Table 4A - Volatile Organic Compound Concentrations, Groundwater Monitoring Wells
- Table 4B - Volatile Organic Compound Concentrations, Residential Wells
- Table 5A - Phthalate Concentrations, Groundwater Monitoring Wells
- Table 5B - Phthalate Concentrations, Residential Wells

**Table 1**  
**Groundwater Elevation Summary**  
**Spickler Monitoring**  
**STS Project No. 84374XA**

Well No.	TPVC	Ground	Depth	Date: 02/15/95		Date: 3/30/95		Date: 4/25/95		Date: 6/5/95		Date: 9/8/95		Date: 9/15/95		Date: 12/15/95		Date: 3/11/96	
	Pipe	Surface	of	Depth	Elev.	Depth	Elev.	Depth	Elev.	Depth	Elev.	Depth	Elev.	Depth	Elev.	Depth	Elev.	Depth	Elev.
	Elev.	Elevation	Well	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water
MW-6D	1307.24	1305.11	62.7	19.60	1287.64	18.36	1288.88	---	---	18.27	1288.97	---	---	19.47	1287.77	18.55	1288.69	18.32	1288.92
MW-6S	1307.23	1304.98	20.1	13.87	1293.36	13.37	1293.86	---	---	12.73	1294.50	---	---	14.02	1293.21	13.16	1294.07	13.88	1293.35
MW-7D	1319.42	1317.09	62.7	30.24	1289.18	29.57	1289.85	---	---	28.85	1290.57	---	---	30.41	1289.01	29.61	1289.81	29.28	1290.14
MW-7S	1319.82	1317.34	24.1	21.29	1298.53	19.15	1300.67	---	---	20.34	1299.48	---	---	23.29	1296.53	20.30	1299.52	20.16	1299.66
MW-8D	1332.27	1329.87	47.6	33.20	1299.07	31.88	1300.39	---	---	29.87	1302.40	---	---	31.97	1300.30	32.44	1299.83	32.82	1299.45
MW-8S	1332.29	1329.86	22.5	14.80	1317.49	8.80	1323.49	---	---	11.22	1321.07	---	---	12.52	1319.77	11.85	1320.44	12.12	1320.17
MW-9S	1311.65	1309.33	28.6	17.93	1293.72	17.50	1294.15	---	---	16.77	1294.88	---	---	18.06	1293.59	17.39	1294.26	16.70	1294.95
MW-10D	1324.29	1322.25	62.6	33.25	1291.04	32.65	1291.64	---	---	32.40	1291.89	---	---	33.90	1290.39	33.05	1291.24	32.99	1291.30
MW-10S	1324.55	1322.48	20.8	8.79	1315.76	4.13	1320.42	---	---	6.92	1317.63	---	---	6.76	1317.79	5.84	1318.71	6.78	1317.77
MW-11S	1329.58	1327.21	20.6	18.60	1310.98	4.44	1325.14	---	---	6.40	1323.18	---	---	8.48	1321.10	8.18	1321.40	8.08	1321.50
MW-12D	1304.94	1302.71	62.5	21.09	1283.85	19.43	1285.51	---	---	19.49	1285.45	---	---	20.82	1284.12	19.81	1285.13	19.43	1285.51
MW-12S	1305.02	1302.74	27.8	14.82	1290.20	12.35	1292.67	---	---	12.92	1292.10	---	---	14.42	1290.60	13.52	1291.50	12.54	1292.48
MW-13D	1305.7	1303.40	62.8	17.65	1288.05	16.53	1289.17	---	---	16.32	1289.38	---	---	17.48	1288.22	16.70	1289.00	16.42	1289.28
MW-13S	1306.08	1303.69	23.6	12.40	1293.68	12.00	1294.08	---	---	11.33	1294.75	---	---	12.57	1293.51	11.85	1294.23	11.48	1294.60
MW-14D	1306.77	1304.74	62.4	18.30	1288.47	17.30	1289.47	---	---	17.07	1289.70	---	---	18.15	1288.62	17.35	1289.42	17.29	1289.48
MW-14S	1306.57	1304.35	26.3	12.45	1294.12	12.15	1294.42	---	---	11.44	1295.13	---	---	12.67	1293.90	12.08	1294.49	11.71	1294.86
MW-15D	1310.82	1305.67	72.6	21.45	1289.37	20.63	1290.19	---	---	20.35	1290.47	---	---	21.31	1289.51	20.70	1290.12	20.54	1290.28
MW-15S	1310.29	1307.95	27.4	14.61	1295.68	14.57	1295.72	---	---	13.85	1296.44	---	---	14.94	1295.35	14.41	1295.88	14.28	1296.01
MW-16S	1323.74	1321.52	20.9	7.80	1315.94	3.12	1320.62	---	---	5.21	1318.53	---	---	6.54	1317.20	5.17	1318.57	5.28	1318.46
MW-17SR	1341.52	1338.90	18.7	16.40	1325.12	14.50	1327.02	---	---	14.85	1326.67	14.78	1326.74	14.95	1326.57	15.75	1325.77	15.28	1326.24
MW-18S	1315.05	1312.89	26.3	14.03	1301.02	14.07	1300.98	---	---	13.32	1301.73	---	---	14.70	1300.35	14.22	1300.83	14.40	1300.65
MW-19D	1334.22	1331.83	52.2	35.00	1299.22	35.73	1298.49	---	---	34.60	1299.62	---	---	35.58	1298.64	35.54	1298.68	35.98	1298.24
MW-19S	1334.34	1332.06	21.1	8.65	1325.69	7.30	1327.04	---	---	6.93	1327.41	---	---	6.95	1327.39	7.18	1327.16	8.01	1326.33
MW-20S	1298.93	1297.01	21.8	6.63	1292.30	5.65	1293.28	---	---	5.49	1293.44	---	---	6.76	1292.17	5.90	1293.03	5.43	1293.50
S1	1331.86	1331.86	21.15	19.11	1312.75	18.80	1313.06	---	---	18.41	1313.45	---	---	18.34	1313.52	--	--	17.20	1314.66
S1A	1331.90	1331.90	49.15	34.00	1297.90	35.75	1296.15	---	---	34.04	1297.86	---	---	34.84	1297.06	--	--	34.25	1297.65
S1AR	1335.41	1332.48	41.9	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	37.54	1297.87
S2	1311.87	1311.90	12	NA	NA	6.05	1305.82	---	---	4.95	1306.92	---	---	5.48	1306.39	--	--	5.76	1306.11
S2A	1311.81	1311.80	24.4	NA	NA	15.00	1296.81	---	---	14.76	1297.05	---	---	15.05	1296.76	--	--	16.14	1295.67
S2AR	1314.93	1312.37	30.8	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	18.99	1295.94
S3	1313.28	1310.10	20.31	17.46	1295.82	17.18	1296.10	---	---	16.07	1297.21	---	---	18.22	1295.06	16.65	1296.63	15.78	1297.50
S3A	1312.71	1310.18	33.9	18.60	1294.11	18.20	1294.51	---	---	17.56	1295.15	---	---	18.82	1293.89	17.95	1294.76	17.80	1294.91
S3AR	1311.76	1308.89	32.7	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	16.62	1295.14
LH-1	1326.76	1324.08	7.1	Dry	Dry	Dry	Dry	6.22	1320.54	6.10	1320.66	6.22	1320.54	6.26	1320.50	--	--	6.74	1320.02
LH-4	1326.99	1325.13	14	13.05	1313.94	13.24	1313.75	13.36	1313.63	13.29	1313.70	13.26	1313.73	13.28	1313.71	--	--	Damage	--
LH-6	1347.35	1344.27	7.72	16.00	1331.35	16.10	1331.25	15.99	1331.36	15.93	1331.42	15.72	1331.63	15.77	1331.58	15.90	1331.45	16.05	1331.30
LH-8	1344.61	1341.74	21.2	18.50	1326.11	17.73	1326.88	17.64	1326.97	17.85	1326.76	17.54	1327.07	17.40	1327.21	18.00	1326.61	17.86	1326.75
LH-9	1334.65	1330.70	11.5	Dry	Dry	Dry	Dry	Dry	Dry	Dry	Dry	Dry	Dry	Dry	Dry	Dry	Dry	Dry	Dry
Sump#2	1328.08	---	---	---	---	---	---	13.50	1314.58	---	---	---	---	---	---	---	---	---	---
Sump#3	1341.46	---	---	---	---	---	---	8.02	1333.44	---	---	---	---	---	---	---	---	---	---

**Notes:**

1. Elevations are in feet relative to Mean Sea Level and depths are in feet.
2. NA = Data not available or well not present at that time.
3. Top of PVC and Ground Surface Elevations were obtained on February 15, 1995.
4. --- = Groundwater Elevations not measured.

PARAMETER

Notes:

- Page 1 of 3

**TABLE 2A**  
**FIELD PARAMETERS**  
**GROUNDWATER MONITORING WELLS**  
**ROUND 1 LONG TERM GROUNDWATER**  
**MONITORING**  
**SPICKLER LANDFILL SITE**

<u>PARAMETER</u>	<u>MW-14S</u>	<u>MW-15S</u>	<u>MW-15D</u>	<u>MW-19S</u>	<u>MW-19S (dupe)</u>	<u>MW-19D</u>	<u>MW-20S</u>	<u>MW-S1</u>	<u>MW-S1A</u>	<u>MW-S1AR</u>
pH (standard units)	6.19	6.26	6.60	6.13	6.17	5.48	6.05	6.72	6.65	6.62
Temperature (degrees Celsius)	7.9	7.0	10.0	11.0	11.0	11.0	6.1	6.1	7.3	7.5
Specific Conductance (umhos/cm)	106	155	33	861	833	74	191	307	1254	3246

Notes:

1. Samples were collected in March 1996

**TABLE 2A  
FIELD PARAMETERS  
GROUNDWATER MONITORING WELLS  
ROUND 1 LONG TERM GROUNDWATER  
MONITORING  
SPICKLER LANDFILL SITE**

<u>PARAMETER</u>	<u>MW-S2</u>	<u>MW-S2A</u>	<u>MW-S2AR</u>	<u>MW-S3</u>	<u>MW-S3A</u>	<u>MW-S3A (dupe)</u>	<u>MW-S3AR</u>
pH (standard units)	6.27	5.90	5.83	6.09	5.53	5.50	6.10
Temperature (degrees Celsius)	6.1	8.0	8.1	6.1	8.0	8.5	6.1
Specific Conductance (umhos/cm)	368	426	301	368	514	507	449

Notes:

1. Samples were collected in March 1996

**TABLE 2B**  
**FIELD PARAMETERS**  
**RESIDENTIAL WELLS**  
**ROUND 1 LONG TERM GROUNDWATER**  
**MONITORING**  
**SPICKLER LANDFILL SITE**

<u>PARAMETER</u>	<u>RW-2543</u>	<u>RW-2543 (dupe)</u>	<u>RW-2551</u>
pH (standard units)	5.93	5.99	6.06
Temperature (degrees Celsius)	10.1	10.1	10.3
Specific Conductance (umhos/cm)	87	86	119

Notes:

1. Samples were collected in March 1996



**Table 3A**  
**Metal and Cyanide Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte, $\mu\text{g/l}$	IDL	CRDL	NR140 PAL	NR140 ES	MW-6D	MW-6S	MW-7D	MW-7S	MW-10S	MW-11S	MW-13D	MW-13S
Arsenic	1.0	10.0	5	50	1 U	2.9 B	1.0 U	1.0 U	1.0 U	1.6 B	1 U	1 U
Barium	0.6	200	400	2000	1.5 U	93.1 U	1.1 U	52.0 U	230	482	2.5 U	433
Chromium	3.6	10	10	100	3.6 U	3.6 U	3.6 U	3.6 U	3.6 U	3.6 U	3.6 U	3.6 U
Cyanide	2.5	10	40	200	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.5 U	2.7 U
Iron	6.6	100	150	300	6.6 U	5090	155	19.9 U	12700	41300	6.6 U	3280
Lead	1.0	3.0	1.5	15	1 U	1 U	1.0 U	1.0 U	1.0 U W2	1 U	1 U	1 U
Manganese	0.3	15	25	50	3.8 U	1320	24.0	12.8 U	798	2970	4.3 U	5960
Mercury	0.03	0.2	0.2	2	0.03 U	0.03 U	0.10 U	0.17 U	0.20 U	0.04 U	0.12U	0.05 U

Notes:

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = analyte not detected above concentration shown

B = analyte detected, but below contract required detection limit

CRQL - Contract Required Detection Limit

IDL - Instrument Detection Limit

W2 - Post digestion spike recovery exceeded upper control limit.

ES Exceedance - [REDACTED]

PAL Exceedance - [REDACTED]

\* MW-S1 did not contain sufficient water to sample for metals and cyanide.

**Table 3A**  
**Metal and Cyanide Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte, $\mu\text{g/l}$	IDL	CRDL	NR140 PAL	NR140 ES	MW-13S	MW-14S	MW-15D	MW-15S	MW-19D	MW-19S	MW-19S	MW-20S
					(Dupe)						(Dupe)	
Arsenic	1.0	10.0	5	50	1 U	1 U	1 U	28.8	1 U	3.5 B	3.2 B	1 U
Barium	0.6	200	400	2000	464	47.1 U	3.9 U	50.2 U	45.3 U	243	235	55.4 U
Chromium	3.6	10	10	100	3.6 U	3.6 U	3.6 U	3.6 U	3.6 U	3.6 U	3.6 U	3.6 U
Cyanide	2.5	10	40	200	2.5 U	2.5 U	2.5 U	4.3 U	2.7 U	3.3 U	2.5 U	2.8 U
Iron	6.6	100	150	300	3940	6.6 U	6.6 U	6.6 U	125	25600	25400	6.6 U
Lead	1.0	3.0	1.5	15	1 U	1 U	1 U	1 U	1 U	1 U	1 U	1 U
Manganese	0.3	15	25	50	6490	6 U	5.3 U	15.4 U	142	1070	1060	12.7 U
Mercury	0.03	0.2	0.2	2	0.13 U	0.15 U	0.03 U	0.07 U	0.03 U	0.03 U	0.03 U	0.03 U

**Notes:**

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = analyte not detected above concentration shown

B = analyte detected, but below contract required detection limit

CRQL - Contract Required Detection Limit

IDL - Instrument Detection Limit

W2 - Post digestion spike recovery exceeded upper control limit.

ES Exceedance -

PAL Exceedance -

\* MW-S1 did not contain sufficient water to sample for metals and cyanide.

**Table 3A**  
**Metal and Cyanide Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte, $\mu\text{g/l}$	IDL	CRDL	NR140 PAL	NR140 ES	MW-S1A	MW-S1*	MW-S1AR	MW-S2	MW-S2A	MW-S2AR	MW-S3	MW-S3A
Arsenic	1.0	10.0	5	50	14.4 U		2.3 U	3.0 U	1.0 U	1.0 U	1.0 U	1.0 U
Barium	0.6	200	400	2000	309		580	1690	137 B	27.1 U	128 B	243
Chromium	3.6	10	10	100	3.6 U		3.6 U	3.6 U	3.6 U	3.6 U	3.6 U	3.6 U
Cyanide	2.5	10	40	200	2.5 U		2.5 U	2.5 U	3 U	2.5 U	2.5 U	2.5 U
Iron	6.6	100	150	300	18900		31800	2130	830	6.6 U	3480	41.5 U
Lead	1.0	3.0	1.5	15	1.0 U		1.0 U	1.0 U W2	1.0 U	1.0 U	1.0 U	1.0 U
Manganese	0.3	15	25	50	5910		12600	6660	3720	131	731	558
Mercury	0.03	0.2	0.2	2	0.17 U		0.3 U	0.22 U	0.19 U	0.12 U	0.37 U	0.32 U

**Notes:**

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = analyte not detected above concentration shown

B = analyte detected, but below contract required detection limit

CRQL - Contract Required Detection Limit

IDL - Instrument Detection Limit

W2 - Post digestion spike recovery exceeded upper control limit.

ES Exceedance - [REDACTED]

PAL Exceedance - [REDACTED]

\* MW-S1 did not contain sufficient water to sample for metals and cyanide.

**Table 3A**  
**Metal and Cyanide Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte $\mu\text{g/l}$	IDL	CRDL	NR140 PAL	NR140 ES	MW-S3A		MW-S3AR	MW-FB01	MW-FB02	MW-FB03	Prep Blank	Prep Blank
					(Dupe)							
Arsenic	1.0	10.0	5	50	1.0 U		1.0 U	1 U	1.0 U	1.0 U	2.220 B	1 U
Barium	0.6	200	400	2000	233		108 B	0.6 U	0.60 U	21.2 B	0.600 U	0.6 U
Chromium	3.6	10	10	100	3.6 U		3.6 U	3.6 U	3.6 U	3.6 U	3.600 U	3.6 U
Cyanide	2.5	10	40	200	2.5 U		2.5 U	3.7 U	2.5 U	2.5 U	2.500 U	2.5 U
Iron	6.6	100	150	300	40.6 U		537	6.6 U	6.6 U	6.6 U	14.429 B	15.359 B
Lead	1.0	3.0	1.5	15	1.0 U		1.0 U	1.2 B	1.0 U	1.2 B	1.000 U	1 U
Manganese	0.3	15	25	50	538		266	4.3 U	3.0 U	7.3 U	2.804 B	3.012 B
Mercury	0.03	0.2	0.2	2	0.31 U		0.22 U	0.03 U	0.16 U	0.17 U	0.118 B	0.079B

Notes:

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = analyte not detected above concentration shown

B = analyte detected, but below contract required detection limit

CRQL - Contract Required Detection Limit

IDL - Instrument Detection Limit

W2 - Post digestion spike recovery exceeded upper control limit.

ES Exceedance - [REDACTED]

PAL Exceedance - [REDACTED]

\* MW-S1 did not contain sufficient water to sample for metals and cyanide.

**Table 3B**  
**Metal and Cyanide Concentrations**  
**Residential Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

<u>Analyte, <math>\mu\text{g/l}</math></u>	<u>IDL</u>	<u>CRDL</u>	<u>NR140 PAL</u>	<u>NR140 ES</u>	RW-2543			
					<u>RW-2543</u>	<u>(Dupe)</u>	<u>RW-2551</u>	<u>RW-FB01</u>
Arsenic	1.0	10.0	5	50	1 U	1 U	1 U	1 U
Barium	0.6	200	400	2000	8.4 B	8.6 B	5.7 B	0.6 U
Chromium	3.6	10	10	100	3.6 U	3.6 U	3.6 U	3.6 U
Cyanide	2.5	10	40	200	2.5 U	2.5 U	2.5 U	2.5 U
Iron	6.6	100	150	300	6.6 U	6.6 U	6.6 U	6.6 U
Lead	1.0	3.0	1.5	15	1 U	1 U	1 U	1 U
Manganese	0.3	15	25	50	7.3 U	7.6 U	5.2 U	3.3 U
Mercury	0.03	0.2	0.2	2	0.03 U	0.03 U	0.03 U	0.03 U

Notes:

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = analyte not detected above concentration shown

B = analyte detected, but below contract required detection limit

CRQL - Contract Required Detection Limit

IDL - Instrument Detection Limit

ES Exceedance -

PAL Exceedance -

**Table 4A**  
**Volatile Organic Compound Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte	CRQL	NR140 PAL	NR140 ES	MW-6D	MW-6S	MW-7D	MW-7S	MW-10S	MW-11S
1,2-Dichlorobenzene	1	60	600	1 U	1 U	1 U	1 U	1 U	1 U
1,3-Dichlorobenzene	1	125	1250	1 U	1 U	1 U	1 U	1 U	1 U
1,4-Dichlorobenzene	1	15	75	1 U	1 U	1 U	1 U	1 U	0.6 J
1,1,1-Trichloroethane	1	40	200	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethane	1	85	850	1 U	2	1 U	1 U	0.1 J	1 U
1,1-Dichloroethene	1	0.7	7	1 U	0.1 J	1 U	1 U	1 U	1 U
1,2-Dibromo-3-chloropropane	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dibromoethane	1	0.005	0.05	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethane	1	0.5	5	1 U	0.8 J	1 U	1 U	1 U	1 U
1,2-Dichloropropane	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
2-Butanone	5	90	460	5 U	5 U	5 U	5 U	5 U	5 U
2-Hexanone	5	--	--	5 U	5 U	5 U	5 U	5 U	5 U
4-Methyl-2-Pentanone (MIBK)	5	50	500	5 U	5 U	5 U	5 U	5 U	5 U
Acetone	5	200	1000	5 U	5 U	5 U	2 U	5 U	5 U
Benzene	1	0.5	5	1 U	3	1 U	1 U	2	0.7 J
Bromodichloromethane	1	0.06	0.6	1 U	1 U	1 U	1 U	1 U	1 U
Bromoform	1	0.44	4.4	1 U	1 U	1 U	1 U	1 U	1 U
Bromomethane	1	1	10	1 U	1 U	1 U	1 U	1 U	1 U
Carbon Disulfide	1	--	--	1 U	1 U	1 U	1 U	1 U	1 U
Carbon Tetrachloride	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
Chlorobenzene	1	20	200	1 U	1 U	1 U	1 U	1 U	1 U
Chloroethane	1	80	400	1 U	1	1 U	1 U	0.2 J	1 U
Chloroform	1	0.6	6	1 U	1 U	1 U	1 U	1 U	1 U
Chloromethane	1	0.3	3	0.6 U	1 U	1 U	1 U	1 U	0.2 U
Cis-1,2-Dichloroethene	1	7	70	1 U	2	1 U	1 U	1 U	1 U
Cis-1,3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
Dibromochloromethane	1	6	60	1 U	1 U	1 U	1 U	1 U	1 U
Ethylbenzene	1	140	700	1 U	1 U	1 U	1 U	9	1 U
Methylene Chloride	2	0.5	5	0.2 U	5 U	0.2 U	0.1 U	0.2 U	0.3 U
Styrene	1	10	100	1 U	1 U	1 U	1 U	1 U	1 U
Tetrachloroethene	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
Toluene	1	68.6	343	1 U	1 U	0.1 U	0.1 U	1 U	1 U
Trans-1,2-Dichloroethene	1	20	100	1 U	1 U	1 U	1 U	1 U	1 U
Trans-1,3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
Trichloroethene	1	0.5	5	1 U	0.9 J	1 U	1 U	1 U	1 U
Vinyl Chloride	1	0.02	0.2	1 U	2	1 U	1 U	0.3 J	1 U
Xylene (total)	1	124	620	1 U	14 U	1 U	1 U	51 X	1 U
Bromochloromethane	1	--	--	1 U	1 U	1 U	1 U	1 U	1 U
Naphthalene	5	8	40	5 U	5 U	5 U	5 U	0.6 U	5 U
Dilution Factor				1.0	1.0	1.0	1.0	1.0	1.0

**Notes:**

Samples collected in March 1996

Units in µg/L

U = compound not detected above concentration listed

B = compound also detected in associated blank

J = compound detected, but below contract required quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

X = Concentration of total xylene. Isomer(s) not identified.

D = Concentration determined on a diluted sample.

PAL Exceedance -

ES Exceedance -

Table 4A

**Volatile Organic Compound Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte	CRQL	NR140 PAL	NR140 ES	MW-13D	MW-13S	MW-13S (Dil)	MW-13S(Dupe)	MW-13S (Dupe Dil)
1,2-Dichlorobenzene	1	60	600	1 U	1 U	5 U	1 U	5 U
1,3-Dichlorobenzene	1	125	1250	1 U	1 U	5 U	1 U	5 U
1,4-Dichlorobenzene	1	15	75	1 U	1 U	5 U	1 U	5 U
1,1,1-Trichloroethane	1	40	200	1 U	1 U	5 U	1 U	5 U
1,1,2,2-Tetrachloroethane	1	0.02	0.2	1 U	1 U	5 U	1 U	5 U
1,1,2-Trichloroethane	1	0.5	5	1 U	1 U	5 U	1 U	5 U
1,1-Dichloroethane	1	85	850	1 U	0.3 J	5 U	0.3 J	5 U
1,1-Dichloroethene	1	0.7	7	1 U	1 U	5 U	1 U	5 U
1,2-Dibromo-3-chloropropane	1	0.02	0.2	1 U	1 U	5 U	1 U	5 U
1,2-Dibromoethane	1	0.005	0.05	1 U	1 U	5 U	1 U	5 U
1,2-Dichloroethane	1	0.5	5	1 U	1 U	5 U	1 U	5 U
1,2-Dichloropropane	1	0.5	5	1 U	1 U	5 U	1 U	5 U
2-Butanone	5	90	460	5 U	5 U	25 U	5 U	25 U
2-Hexanone	5	--	--	5 U	5 U	25 U	5 U	25 U
4-Methyl-2-Pentanone (MIBK)	5	50	500	5 U	5 U	25 U	5 U	25 U
Acetone	5	200	1000	5 U	5 U	25 U	5 U	25 U
Benzene	1	0.5	5	1 U	1	1 DJ	1	1 DJ
Bromodichloromethane	1	0.06	0.6	1 U	1 U	5 U	1 U	5 U
Bromoform	1	0.44	4.4	1 U	1 U	5 U	1 U	5 U
Bromomethane	1	1	10	1 U	1 U	5 U	1 U	5 U
Carbon Disulfide	1	--	--	1 U	1 U	5 U	1 U	5 U
Carbon Tetrachloride	1	0.5	5	1 U	1 U	5 U	1 U	5 U
Chlorobenzene	1	20	200	1 U	1 U	5 U	1 U	5 U
Chloroethane	1	80	400	1 U	1 U	5 U	1 U	5 U
Chloroform	1	0.6	6	1 U	1 U	5 U	1 U	5 U
Chloromethane	1	0.3	3	0.4 U	0.2 U	5 U	1 U	5 U
Cis-1,2-Dichloroethene	1	7	70	1 U	0.7 J	0.5 DJ	0.8 J	0.6 DJ
Cis-1-3-Dichloropropene	1	0.02	0.2	1 U	1 U	5 U	1 U	5 U
Dibromochloromethane	1	6	60	1 U	1 U	5 U	1 U	5 U
Ethylbenzene	1	140	700	1 U	21	18 D	20	19 D
Methylene Chloride	2	0.5	5	0.2 U	0.4 U	3 U	0.5 U	3 U
Styrene	1	10	100	1 U	1 U	5 U	1 U	5 U
Tetrachloroethene	1	0.5	5	1 U	1 U	5 U	1 U	5 U
Toluene	1	68.6	343	1 U	0.2 U	5 U	0.8 U	5 U
Trans-1-2-Dichloroethene	1	20	100	1 U	1 U	5 U	1 U	5 U
Trans-1-3-Dichloropropene	1	0.02	0.2	1 U	1 U	5 U	1 U	5 U
Trichloroethene	1	0.5	5	1 U	0.2 J	5 U	0.3 J	5 U
Vinyl Chloride	1	0.02	0.2	1 U	0.3 J	5 U	0.2 J	5 U
Xylene (total)	1	124	620	1 U	78 BXE	78 DX	73 BXE	87 DX
Bromochloromethane	1	--	--	1 U	1 U	5 U	1 U	5 U
Naphthalene	5	8	40	5 U	5 U	0.8 U	5 U	25 U
Dilution Factor				1.0	1.0	5.0	1.0	5.0

**Notes:**

Samples collected in March 1996

Units in µg/L

U = compound not detected above concentration listed

B = compound also detected in associated blank

J = compound detected, but below contract required quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

X = Concentration of total xylene. Isomer(s) not identified.

D = Concentration determined on a diluted sample.

PAL Exceedance -

ES Exceedance -

Table 4A

**Volatile Organic Compound Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte	CRQL	NR140 PAL	NR140 ES	MW-14S	MW-15D	MW-15S	MW-19D	MW-19S	MW-19S (Dupe)
1,2-Dichlorobenzene	1	60	600	1 U	1 U	1 U	1 U	1 U	1 U
1,3-Dichlorobenzene	1	125	1250	1 U	1 U	1 U	1 U	1 U	1 U
1,4-Dichlorobenzene	1	15	75	1 U	1 U	1 U	1 U	1 U	1 U
1,1,1-Trichloroethane	1	40	200	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethane	1	85	850	1 U	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethene	1	0.7	7	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dibromo-3-chloropropane	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dibromoethane	1	0.005	0.05	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethane	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloropropane	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
2-Butanone	5	90	460	5 U	5 U	5 U	5 U	5 U	5 U
2-Hexanone	5	--	--	5 U	5 U	5 U	5 U	5 U	5 U
4-Methyl-2-Pentanone (MIBK)	5	50	500	5 U	5 U	5 U	5 U	5 U	5 U
Acetone	5	200	1000	5 U	5 U	5 U	2 J	5 U	5 U
Benzene	1	0.5	5	1 U	1 U	1 U	1 U	0.1 J	0.1 J
Bromodichloromethane	1	0.06	0.6	1 U	1 U	1 U	1 U	1 U	1 U
Bromoform	1	0.44	4.4	1 U	1 U	1 U	1 U	1 U	1 U
Bromomethane	1	1	10	1 U	1 U	1 U	1 U	1 U	1 U
Carbon Disulfide	1	--	--	1 U	1 U	1 U	1 U	1 U	1 U
Carbon Tetrachloride	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
Chlorobenzene	1	20	200	1 U	1 U	1 U	1 U	1 U	1 U
Chloroethane	1	80	400	1 U	1 U	1 U	1 U	1 U	1 U
Chloroform	1	0.6	6	1 U	1 U	1 U	1 U	1 U	1 U
Chloromethane	1	0.3	3	1 U	0.3 U	0.2 U	0.3 U	0.2 U	0.2 U
Cis-1,2-Dichloroethene	1	7	70	1 U	1 U	1 U	1 U	1 U	1 U
Cis-1-3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
Dibromochloromethane	1	6	60	1 U	1 U	1 U	1 U	1 U	1 U
Ethylbenzene	1	140	700	1 U	1 U	1 U	1 U	0.5 J	0.6 J
Methylene Chloride	2	0.5	5	0.3 U	0.2 U	0.2 U	0.2 U	0.2 U	0.3 U
Styrene	1	10	100	1 U	1 U	1 U	1 U	1 U	1 U
Tetrachloroethene	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
Toluene	1	68.6	343	0.2 U	1 U	0.1 U	1 U	1 U	1 U
Trans-1-2-Dichloroethene	1	20	100	1 U	1 U	1 U	1 U	1 U	1 U
Trans-1-3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
Trichloroethene	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
Vinyl Chloride	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
Xylene (total)	1	124	620	1 U	1 U	1 U	1 U	5 X	6 X
Bromochloromethane	1	--	--	1 U	1 U	1 U	1 U	1 U	1 U
Naphthalene	5	8	40	5 U	5 U	5 U	5 U	5 U	5 U
Dilution Factor				1.0	1.0	1.0	1.0	1.0	1.0

**Notes:**

Samples collected in March 1996

Units in µg/L

U = compound not detected above concentration listed

B = compound also detected in associated blank

J = compound detected, but below contract required quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

X = Concentration of total xylene. Isomer(s) not identified.

D = Concentration determined on a diluted sample.

PAL Exceedance -

ES Exceedance -



**Table 4A**  
**Volatile Organic Compound Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte	CRQL	NR140 PAL	NR140 ES	MW-20S	MW-S1	MW-S1A	MW-S1A (Dil)	MW-S1AR
1,2-Dichlorobenzene	1	60	600	1 U	1 U	1 U	5 U	1 U
1,3-Dichlorobenzene	1	125	1250	1 U	1 U	1 U	5 U	1 U
1,4-Dichlorobenzene	1	15	75	1 U	1 U	0.2 J	5 U	0.6 J
1,1,1-Trichloroethane	1	40	200	1 U	1 U	1 U	5 U	1 U
1,1,2,2-Tetrachloroethane	1	0.02	0.2	1 U	1 U	1 U	5 U	1 U
1,1,2-Trichloroethane	1	0.5	5	1 U	1 U	1 U	5 U	1 U
1,1-Dichloroethane	1	85	850	1 U	1 U	1	1 DJ	5
1,1-Dichloroethene	1	0.7	7	1 U	1 U	1 U	5 U	0.1 J
1,2-Dibromo-3-chloropropane	1	0.02	0.2	1 U	1 U	1 U	5 U	1 U
1,2-Dibromoethane	1	0.005	0.05	1 U	1 U	1 U	5 U	1 U
1,2-Dichloroethane	1	0.5	5	1 U	1 U	1 U	5 U	0.3 J
1,2-Dichloropropane	1	0.5	5	1 U	1 U	1 U	5 U	1 U
2-Butanone	5	90	460	5 U	5 U	5 U	25 U	20
2-Hexanone	5	--	--	5 U	5 U	5 U	25 U	5 U
4-Methyl-2-Pentanone (MIBK)	5	50	500	5 U	5 U	0.3 J	25 U	15
Acetone	5	200	1000	5 U	4 U	5 U	25 U	59 U
Benzene	1	0.5	5	0.8 J	1 U	0.6 J	0.9 DJ	2
Bromodichloromethane	1	0.06	0.6	1 U	1 U	1 U	5 U	1 U
Bromoform	1	0.44	4.4	1 U	1 U	1 U	5 U	1 U
Bromomethane	1	1	10	1 U	1 U	1 U	5 U	1 U
Carbon Disulfide	1	--	--	1 U	1 U	0.1 J	5 U	1 U
Carbon Tetrachloride	1	0.5	5	1 U	1 U	1 U	5 U	1 U
Chlorobenzene	1	20	200	1 U	1 U	1 U	5 U	1 U
Chloroethane	1	80	400	1 U	4 U	1	5 U	0.6 J
Chloroform	1	0.6	6	1 U	4 U	0.1 J	5 U	2
Chloromethane	1	0.3	3	0.2 U	0.4 U	1 U	0.8 U	0.5 U
Cis-1,2-Dichloroethene	1	7	70	0.3 J	1 U	4.0	4 DJ	22
Cis-1-3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	5 U	1 U
Dibromochloromethane	1	6	60	1 U	1 U	1 U	5 U	1 U
Ethylbenzene	1	140	700	1 U	1 U	2	1 DJ	6
Methylene Chloride	2	0.5	5	0.2 U	4 U	5 U	7 U	5 U
Styrene	1	10	100	1 U	1 U	1 U	5 U	1 U
Tetrachloroethene	1	0.5	5	1 U	1 U	0.3 J	5 U	0.4 J
Toluene	1	68.6	343	1 U	1 U	17	16 D	43 E
Trans-1-2-Dichloroethene	1	20	100	1 U	1 U	0.1 J	5 U	0.4 J
Trans-1-3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	5 U	1 U
Trichloroethene	1	0.5	5	1 U	1 U	1 E	1 DJ	4
Vinyl Chloride	1	0.02	0.2	0.1 J	4 U	58 E	35 D	140 E
Xylene (total)	1	124	620	1 U	1 U	9 BX	8 U	24 BX
Bromochloromethane	1	--	--	1 U	1 U	1 U	1 U	1 U
Naphthalene	5	8	40	5 U	0.2 U	0.2 U	25 U	0.4 U
Dilution Factor				1.0	1.0	1.0	5.0	1.0

**Notes:**

Samples collected in March 1996

Units in µg/L

U = compound not detected above concentration listed

B = compound also detected in associated blank

J = compound detected, but below contract required quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

X = Concentration of total xylene. Isomer(s) not identified.

D = Concentration determined on a diluted sample.

PAL Exceedance -

ES Exceedance -

Table 4A

**Volatile Organic Compound Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte	CRQL	NR140 PAL	NR140 ES	MW-S1AR (Dil)	MW-S2	MW-S2A	MW-S2AR	MW-S3	MW-S3 (Dil)
1,2-Dichlorobenzene	1	60	600	10 U	1 U	1 U	1 U	1 U	5 U
1,3-Dichlorobenzene	1	125	1250	10 U	1 U	1 U	1 U	1 U	5 U
1,4-Dichlorobenzene	1	15	75	10 U	1 U	1 U	1 U	0.2 J	5 U
1,1,1-Trichloroethane	1	40	200	10 U	1 U	1 U	1 U	1 U	5 U
1,1,2,2-Tetrachloroethane	1	0.02	0.2	10 U	1 U	1 U	1 U	1 U	5 U
1,1,2-Trichloroethane	1	0.5	5	10 U	1 U	1 U	1 U	1 U	5 U
1,1-Dichloroethane	1	85	850	4 DJ	1 U	0.6 J	0.3 J	2	2 DJ
1,1-Dichloroethene	1	0.7	7	10 U	1 U	1 U	1 U	1 U	5 U
1,2-Dibromo-3-chloropropane	1	0.02	0.2	10 U	1 U	1 U	1 U	1 U	5 U
1,2-Dibromoethane	1	0.005	0.05	10 U	1 U	1 U	1 U	1 U	5 U
1,2-Dichloroethane	1	0.5	5	10 U	1 U	1 U	1 U	1 U	5 U
1,2-Dichloropropane	1	0.5	5	10 U	1 U	1 U	1 U	1 U	5 U
2-Butanone	5	90	460	50 U	5 U	5 U	5 U	5 U	25 U
2-Hexanone	5	—	—	50 U	5 U	5 U	5 U	5 U	25 U
4-Methyl-2-Pentanone (MIBK)	5	50	500	13 U	5 U	5 U	5 U	5 U	25 U
Acetone	5	200	1000	50 U	5 U	5 U	5 U	5 U	25 U
Benzene	1	0.5	5	2 DJ	0.2 J	0.8 J	0.1 J	3	2 DJ
Bromodichloromethane	1	0.06	0.6	10 U	1 U	1 U	1 U	1 U	5 U
Bromoform	1	0.44	4.4	10 U	1 U	1 U	1 U	1 U	5 U
Bromomethane	1	1	10	10 U	1 U	1 U	1 U	1 U	5 U
Carbon Disulfide	1	—	—	10 U	1 U	1 U	1 U	1 U	5 U
Carbon Tetrachloride	1	0.5	5	10 U	1 U	1 U	1 U	1 U	5 U
Chlorobenzene	1	20	200	10 U	1 U	1 U	1 U	1 U	5 U
Chloroethane	1	80	400	10 U	1 U	0.1 J	1 U	3	3 DJ
Chloroform	1	0.6	6	1 DJ	1 U	1 U	1 U	8 U	5 U
Chloromethane	1	0.3	3	10 U	1 U	1 U	1 U	0.7 U	0.6 U
Cis-1,2-Dichloroethene	1	7	70	20 D	1 U	0.4 J	1 U	0.7 J	0.6 DJ
Cis-1-3-Dichloropropene	1	0.02	0.2	10 U	1 U	1 U	1 U	1 U	5 U
Dibromochloromethane	1	6	60	10 U	1 U	1 U	1 U	1 U	5 U
Ethylbenzene	1	140	700	4 DJ	1 U	2	1 U	20	19 D
Methylene Chloride	2	0.5	5	10 U	4 U	3 U	4 U	3 U	5 U
Styrene	1	10	100	10 U	1 U	1 U	1 U	1 U	5 U
Tetrachloroethene	1	0.5	5	10 U	1 U	1 U	1 U	1 U	5 U
Toluene	1	68.6	343	45 D	1 U	0.7 U	0.2 U	0.2 U	5 U
Trans-1-2-Dichloroethene	1	20	100	10 U	1 U	1 U	1 U	1 U	5 U
Trans-1-3-Dichloropropene	1	0.02	0.2	10 U	1 U	1 U	1 U	1 U	5 U
Trichloroethene	1	0.5	5	4 DJ	1 U	1 U	1 U	1 U	5 U
Vinyl Chloride	1	0.02	0.2	110 D	1 U	0.2 J	1 U	2	2 DJ
Xylene (total)	1	124	620	22 BDX	6 X	7 BX	0.2 U	80 XE	84 BDX
Bromochloromethane	1	—	—	10 U	1 U	1 U	1 U	1 U	5 U
Naphthalene	5	8	40	50 U	0.1 U	5 U	0.2 U	0.8 U	0.7 U
Dilution Factor				10.0	1.0	1.0	1.0	1.0	5.0

**Notes:**

Samples collected in March 1996

Units in µg/L

U = compound not detected above concentration listed

B = compound also detected in associated blank

J = compound detected, but below contract required quantitation limit

— = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

X = Concentration of total xylene. Isomer(s) not identified.

D = Concentration determined on a diluted sample.

PAL Exceedance -

ES Exceedance -

Table 4A

**Volatile Organic Compound Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte	CRQL	NR140 PAL	NR140 ES	MW-S3A	MW-S3A (Dupe)	MW-S3AR	MW-FB02	MW-FB03	MW-TB02
1,2-Dichlorobenzene	1	60	600	1 U	1 U	1 U	1 U	1 U	1 U
1,3-Dichlorobenzene	1	125	1250	1 U	1 U	1 U	1 U	1 U	1 U
1,4-Dichlorobenzene	1	15	75	2	2	0.4 J	1 U	1 U	1 U
1,1,1-Trichloroethane	1	40	200	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethane	1	85	850	13	13	12	1 U	1 U	1 U
1,1-Dichloroethene	1	0.7	7	0.2 J	0.2 J	0.2 J	1 U	1 U	1 U
1,2-Dibromo-3-chloropropane	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dibromoethane	1	0.005	0.05	1 U	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethane	1	0.5	5	4	4	4	1 U	1 U	1 U
1,2-Dichloropropane	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
2-Butanone	5	90	460	5 U	5 U	5 U	5	5 U	5 U
2-Hexanone	5	--	--	5 U	5 U	5 U	5 U	5 U	5 U
4-Methyl-2-Pentanone (MIBK)	5	50	500	5 U	5 U	5 U	5 U	5 U	5 U
Acetone	5	200	1000	5 U	5 U	5 U	8	7	5 U
Benzene	1	0.5	5	3	3	1.0	1 U	1 U	1 U
Bromodichloromethane	1	0.06	0.6	1 U	1 U	0.3 J	1 U	1 U	1 U
Bromoform	1	0.44	4.4	1 U	1 U	1 U	1 U	1 U	1 U
Bromomethane	1	1	10	1 U	1 U	1 U	1 U	1 U	1 U
Carbon Disulfide	1	--	--	1 U	1 U	1 U	1 U	1 U	1 U
Carbon Tetrachloride	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
Chlorobenzene	1	20	200	1 U	1 U	1 U	1 U	1 U	1 U
Chloroethane	1	80	400	10	9	6	1 U	1 U	2 U
Chloroform	1	0.6	6	1 U	1 U	0.3 J	1 U	1 U	2 U
Chloromethane	1	0.3	3	0.4 U	0.4 U	1 U	1 U	1 U	0.4 J
Cis-1,2-Dichloroethene	1	7	70	5	6	6	1 U	1 U	1 U
Cis-1-3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
Dibromochloromethane	1	6	60	1 U	1 U	0.2 J	1 U	1 U	1 U
Ethylbenzene	1	140	700	1 U	1 U	1 U	1 U	1 U	1 U
Methylene Chloride	2	0.5	5	6 U	5 U	6 U	0.2 U	6 B	0.4 JB
Styrene	1	10	100	1 U	1 U	1 U	1 U	1 U	1 U
Tetrachloroethene	1	0.5	5	1 U	1 U	1 U	1 U	1 U	1 U
Toluene	1	68.6	343	0.2 U	0.1 U	0.3 U	0.1 J	0.2 J	1 U
Trans-1-2-Dichloroethene	1	20	100	1 U	1 U	1 U	1 U	1 U	1 U
Trans-1-3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U	1 U
Trichloroethene	1	0.5	5	0.2 J	0.2 J	0.2 J	1 U	1 U	1 U
Vinyl Chloride	1	0.02	0.2	5	4	2	1 U	1 U	2 U
Xylene (total)	1	124	620	2 U	2 U	0.5 U	1 U	0.1 JX	1 U
Bromochloromethane	1	--	--	1 U	1 U	1 U	1 U	1 U	1 U
Naphthalene	5	8	40	0.9 U	0.9 U	1 U	5 U	5 U	5 U
Dilution Factor				1.0	1.0	1.0	1.0	1.0	1.0

**Notes:**

Samples collected in March 1996

Units in µg/L

U = compound not detected above concentration listed

B = compound also detected in associated blank

J = compound detected, but below contract required quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

X = Concentration of total xylene. Isomer(s) not identified.

D = Concentration determined on a diluted sample.

PAL Exceedance -

ES Exceedance -

Table 4A

**Volatile Organic Compound Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte	CRQL	NR140 PAL	NR140 ES	MW-TB03	MW-FB01	MW-TB01	Method Blank 01	Method Blank 16
1,2-Dichlorobenzene	1	60	600	1 U	1 U	1 U	0.1 J	1 U
1,3-Dichlorobenzene	1	125	1250	1 U	1 U	1 U	1 U	1 U
1,4-Dichlorobenzene	1	15	75	1 U	1 U	1 U	1 U	1 U
1,1,1-Trichloroethane	1	40	200	1 U	1 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane	1	0.5	5	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethane	1	85	850	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethene	1	0.7	7	1 U	1 U	1 U	1 U	1 U
1,2-Dibromo-3-chloropropane	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U
1,2-Dibromoethane	1	0.005	0.05	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethane	1	0.5	5	1 U	1 U	1 U	1 U	1 U
1,2-Dichloropropane	1	0.5	5	1 U	1 U	1 U	1 U	1 U
2-Butanone	5	90	460	5 U	5 U	5 U	5 U	5 U
2-Hexanone	5	--	--	5 U	5 U	5 U	1 J	5 U
4-Methyl-2-Pentanone (MIBK)	5	50	500	5 U	5 U	5 U	0.8 J	5 U
Acetone	5	200	1000	3 J	7	4 J	5 U	5 U
Benzene	1	0.5	5	1 U	1 U	1 U	1 U	1 U
Bromodichloromethane	1	0.06	0.6	1 U	1 U	1 U	1 U	1 U
Bromoform	1	0.44	4.4	1 U	1 U	1 U	1 U	1 U
Bromomethane	1	1	10	1 U	1 U	1 U	1 U	1 U
Carbon Disulfide	1	--	--	1 U	1 U	1 U	1 U	1 U
Carbon Tetrachloride	1	0.5	5	1 U	1 U	1 U	1 U	1 U
Chlorobenzene	1	20	200	1 U	1 U	1 U	1 U	1 U
Chloroethane	1	80	400	3 U	1 U	1 U	1 U	1 U
Chloroform	1	0.6	6	3 U	1 U	1 U	1 U	1 U
Chloromethane	1	0.3	3	1 U	0.4 J	0.5 J	1 U	1 U
Cis-1,2-Dichloroethene	1	7	70	1 U	1 U	1 U	1 U	1 U
Cis-1-3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U
Dibromochloromethane	1	6	60	1 U	1 U	1 U	1 U	1 U
Ethylbenzene	1	140	700	1 U	1 U	1 U	1 U	1 U
Methylene Chloride	2	0.5	5	8 B	0.2 U	4 U	0.5 J	0.9 J
Styrene	1	10	100	1 U	1 U	1 U	1 U	1 U
Tetrachloroethene	1	0.5	5	1 U	1 U	1 U	1 U	1 U
Toluene	1	68.6	343	0.1 J	0.2 J	1 U	1 U	0.2 J
Trans-1-2-Dichloroethene	1	20	100	1 U	1 U	1 U	1 U	1 U
Trans-1-3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U
Trichloroethene	1	0.5	5	1 U	1 U	1 U	1 U	1 U
Vinyl Chloride	1	0.02	0.2	3 U	1 U	1 U	1 U	1 U
Xylene (total)	1	124	620	1 U	1 U	1 U	0.1 JX	0.5 JX
Bromochloromethane	1	--	--	1 U	1 U	1 U	1 U	1 U
Naphthalene	5	8	40	0.1 U	5 U	5 U	3 J	0.4 J
Dilution Factor				1.0	1.0	1.0	1.0	1.0

**Notes:**

Samples collected in March 1996

Units in µg/L

U = compound not detected above concentration listed

B = compound also detected in associated blank

J = compound detected, but below contract required quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

X = Concentration of total xylene. Isomer(s) not identified.

D = Concentration determined on a diluted sample.

PAL Exceedance - [REDACTED]

ES Exceedance - [REDACTED]

Table 4A

**Volatile Organic Compound Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte	CRQL	NR140 PAL	NR140 ES	Method Blank 17	Method Blank 18	Method Blank 20	Method Blank 36
1,2-Dichlorobenzene	1	60	600	1 U	1 U	1 U	1 U
1,3-Dichlorobenzene	1	125	1250	1 U	1 U	1 U	1 U
1,4-Dichlorobenzene	1	15	75	1 U	1 U	1 U	1 U
1,1,1-Trichloroethane	1	40	200	1 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	1	0.02	0.2	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane	1	0.5	5	1 U	1 U	1 U	1 U
1,1-Dichloroethane	1	85	850	1 U	1 U	1 U	1 U
1,1-Dichloroethene	1	0.7	7	1 U	1 U	1 U	1 U
1,2-Dibromo-3-chloropropane	1	0.02	0.2	1 U	1 U	1 U	1 U
1,2-Dibromoethane	1	0.005	0.05	1 U	1 U	1 U	1 U
1,2-Dichloroethane	1	0.5	5	1 U	1 U	1 U	1 U
1,2-Dichloropropane	1	0.5	5	1 U	1 U	1 U	1 U
2-Butanone	5	90	460	5 U	5 U	5 U	5 U
2-Hexanone	5	--	--	5 U	5 U	5 U	5 U
4-Methyl-2-Pentanone (MIBK)	5	50	500	5 U	5 U	5 U	5 U
Acetone	5	200	1000	5 U	5 U	5 U	5 U
Benzene	1	0.5	5	1 U	1 U	1 U	1 U
Bromodichloromethane	1	0.06	0.6	1 U	1 U	1 U	1 U
Bromoform	1	0.44	4.4	1 U	1 U	1 U	1 U
Bromomethane	1	1	10	1 U	1 U	1 U	1 U
Carbon Disulfide	1	--	--	1 U	1 U	1 U	1 U
Carbon Tetrachloride	1	0.5	5	1 U	1 U	1 U	1 U
Chlorobenzene	1	20	200	1 U	1 U	1 U	1 U
Chloroethane	1	80	400	1 U	1 U	1 U	1 U
Chloroform	1	0.6	6	1 U	1 U	1 U	1 U
Chloromethane	1	0.3	3	1 U	1 U	1 U	1 U
Cis-1,2-Dichloroethene	1	7	70	1 U	1 U	1 U	1 U
Cis-1,3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U
Dibromochloromethane	1	6	60	1 U	1 U	1 U	1 U
Ethylbenzene	1	140	700	1 U	1 U	1 U	1 U
Methylene Chloride	2	0.5	5	0.9 J	0.7 J	0.2 J	0.3 J
Styrene	1	10	100	1 U	1 U	1 U	1 U
Tetrachloroethene	1	0.5	5	1 U	1 U	1 U	1 U
Toluene	1	68.6	343	1 U	1 U	1 U	1 U
Trans-1,2-Dichloroethene	1	20	100	1 U	1 U	1 U	1 U
Trans-1,3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U
Trichloroethene	1	0.5	5	1 U	1 U	1 U	1 U
Vinyl Chloride	1	0.02	0.2	1 U	1 U	1 U	1 U
Xylene (total)	1	124	620	1 U	1 U	1 U	1 U
Bromochloromethane	1	--	--	1 U	1 U	1 U	1 U
Naphthalene	5	8	40	0.6 J	0.6 J	0.5 J	0.7 J
Dilution Factor				1.0	1.0	1.0	1.0

**Notes:**

Samples collected in March 1996

Units in µg/L

U = compound not detected above concentration listed

B = compound also detected in associated blank

J = compound detected, but below contract required quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

X = Concentration of total xylene. Isomer(s) not identified.

D = Concentration determined on a diluted sample.

PAL Exceedance -

ES Exceedance -

**Table 4A**  
**Volatile Organic Compound Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte	CRQL	NR140 PAL	NR140 ES	Method Blank 37	Storage Blank 031596	Storage Blank 031496
1,2-Dichlorobenzene	1	60	600	1 U	1 U	1 U
1,3-Dichlorobenzene	1	125	1250	1 U	1 U	1 U
1,4-Dichlorobenzene	1	15	75	1 U	1 U	1 U
1,1,1-Trichloroethane	1	40	200	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	1	0.02	0.2	1 U	1 U	1 U
1,1,2-Trichloroethane	1	0.5	5	1 U	1 U	1 U
1,1-Dichloroethane	1	85	850	1 U	1 U	1 U
1,1-Dichloroethene	1	0.7	7	1 U	1 U	1 U
1,2-Dibromo-3-chloropropane	1	0.02	0.2	1 U	1 U	1 U
1,2-Dibromoethane	1	0.005	0.05	1 U	1 U	1 U
1,2-Dichloroethane	1	0.5	5	1 U	1 U	1 U
1,2-Dichloropropane	1	0.5	5	1 U	1 U	1 U
2-Butanone	5	90	460	5 U	5 U	5 U
2-Hexanone	5	--	--	5 U	5 U	5 U
4-Methyl-2-Pentanone (MIBK)	5	50	500	5 U	5 U	5 U
Acetone	5	200	1000	5 U	5 U	5 U
Benzene	1	0.5	5	1 U	1 U	1 U
Bromodichloromethane	1	0.06	0.6	1 U	1 U	1 U
Bromoform	1	0.44	4.4	1 U	1 U	1 U
Bromomethane	1	1	10	1 U	1 U	1 U
Carbon Disulfide	1	--	--	1 U	1 U	1 U
Carbon Tetrachloride	1	0.5	5	1 U	1 U	1 U
Chlorobenzene	1	20	200	1 U	1 U	1 U
Chloroethane	1	80	400	1 U	1 U	1 U
Chloroform	1	0.6	6	1 U	1 U	1 U
Chloromethane	1	0.3	3	1 U	1 U	1 U
Cis-1,2-Dichloroethene	1	7	70	1 U	1 U	1 U
Cis-1,3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U
Dibromochloromethane	1	6	60	1 U	1 U	1 U
Ethylbenzene	1	140	700	1 U	1 U	1 U
Methylene Chloride	2	0.5	5	0.4 J	1 BJ	0.9 BJ
Styrene	1	10	100	1 U	1 U	1 U
Tetrachloroethene	1	0.5	5	1 U	1 U	1 U
Toluene	1	68.6	343	1 U	0.2 J	0.2 J
Trans-1,2-Dichloroethene	1	20	100	1 U	1 U	1 U
Trans-1,3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U
Trichloroethene	1	0.5	5	1 U	1 U	1 U
Vinyl Chloride	1	0.02	0.2	1 U	1 U	1 U
Xylene (total)	1	124	620	0.1 JX	0.6 JX	0.6 JX
Bromochloromethane	1	--	--	1 U	1 U	1 U
Naphthalene	5	8	40	1 J	0.2 BJ	0.3 BJ
Dilution Factor				1.0	1.0	1.0

**Notes:**

Samples collected in March 1996

Units in µg/L

U = compound not detected above concentration listed

B = compound also detected in associated blank

J = compound detected, but below contract required quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

X = Concentration of total xylene. Isomer(s) not identified.

D = Concentration determined on a diluted sample.

PAL Exceedance - [REDACTED]

ES Exceedance - [REDACTED]

**Table 4B**  
**Volatile Organic Compound Concentrations**  
**Residential Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte, µg/l	CRQL	NR140 PAL	NR140 ES	RW-TB01	RW-2543	RW-2543 (Dupe)	RW-2551	RW-FB01
1,2-Dichlorobenzene	1	60	600	1 U	1 U	1 U	1 U	1 U
1,3-Dichlorobenzene	1	125	1250	1 U	1 U	1 U	1 U	1 U
1,4-Dichlorobenzene	1	15	75	1 U	1 U	1 U	1 U	1 U
1,1,1-Trichloroethane	1	40	200	1 U	1 U	1 U	1 U	1 U
1,1,2,2-Tetrachloroethane	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U
1,1,2-Trichloroethane	1	0.5	5	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethane	1	85	850	1 U	1 U	1 U	1 U	1 U
1,1-Dichloroethene	1	0.7	7	1 U	1 U	1 U	1 U	1 U
1,2-Dibromo-3-chloropropane	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U
1,2-Dibromoethane	1	0.005	0.05	1 U	1 U	1 U	1 U	1 U
1,2-Dichloroethane	1	0.5	5	1 U	1 U	1 U	1 U	1 U
1,2-Dichloropropane	1	0.5	5	1 U	1 U	1 U	1 U	1 U
2-Butanone	5	90	460	5 U	5 U	5 U	5 U	4 J
2-Hexanone	5	--	--	5 U	5 U	5 U	5 U	5 U
4-Methyl-2-Pentanone (MIBK)	5	50	500	5 U	5 U	5 U	5 U	5 U
Acetone	5	200	1000	3 J	5 U	3 U	5 U	7
Benzene	1	0.5	5	1 U	1 U	1 U	1 U	1 U
Bromodichloromethane	1	0.06	0.6	1 U	1 U	1 U	1 U	1 U
Bromoform	1	0.44	4.4	1 U	1 U	1 U	1 U	1 U
Bromomethane	1	1	10	1 U	1 U	1 U	1 U	1 U
Carbon Disulfide	1	--	--	1 U	1 U	1 U	1 U	1 U
Carbon Tetrachloride	1	0.5	5	1 U	1 U	1 U	1 U	1 U
Chlorobenzene	1	20	200	1 U	1 U	1 U	1 U	1 U
Chloroethane	1	80	400	1 U	1 U	1 U	1 U	1 U
Chloroform	1	0.6	6	1 U	1 U	1 U	1 U	1 U
Chloromethane	1	0.3	3	0.5 J	0.6 U	1 U	0.8 U	0.5 J
Cis-1,2-Dichloroethene	1	7	70	1 U	1 U	1 U	1 U	1 U
Cis-1,3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U
Dibromochloromethane	1	6	60	1 U	1 U	1 U	1 U	1 U
Ethylbenzene	1	140	700	1 U	1 U	1 U	1 U	1 U
Methylene Chloride	2	0.5	5	0.5 U	0.2 U	0.3 U	0.2 U	0.3 U
Styrene	1	10	100	1 U	1 U	1 U	1 U	1 U
Tetrachloroethene	1	0.5	5	1 U	1 U	1 U	1 U	1 U
Toluene	1	68.6	343	1 U	1 U	1 U	1 U	0.2 J
Trans-1,2-Dichloroethene	1	20	100	1 U	1 U	1 U	1 U	1 U
Trans-1,3-Dichloropropene	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U
Trichloroethene	1	0.5	5	1 U	1 U	1 U	1 U	1 U
Vinyl Chloride	1	0.02	0.2	1 U	1 U	1 U	1 U	1 U
Xylene (total)	1	124	620	1 U	1 U	1 U	1 U	1 U
Bromochloromethane	1	--	--	1 U	1 U	1 U	1 U	1 U
Naphthalene	5	8	40	5 U	5 U	5 U	5 U	5 U
Dilution Factor				1.0	1.0	1.0	1.0	1.0

**Notes:**

Samples collected in March 1996

Units in µg/L

U = compound not detected above concentration listed

B = compound also detected in associated blank

J = compound detected, but below contract required quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

X = Concentration of total xylene. Isomer(s) not identified.

PAL Exceedance - [REDACTED]

ES Exceedance - [REDACTED]

**Table 5A**  
**Phthalate Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

<u>Analyte, <math>\mu\text{g/l}</math></u>	<u>CRQL</u>	<u>NR140 PAL</u>	<u>NR140 ES</u>	<u>MW-6D</u>	<u>MW-6S</u>	<u>MW-7D</u>	<u>MW-7S</u>	<u>MW-10S</u>	<u>MW-11S</u>	<u>MW-13D</u>	<u>MW-13S</u>
bis(2-Ethylhexyl)Phthalate	10	0.6	6	12 U	0.8 U	0.9 U	2 U	3 U	2 U	1 U	1 U
Di-n-Butylphthalate	10	--	--	0.5 U	0.7 U	0.4 U	0.5 U	0.7 U	0.6 U	1 U	0.7 U
Diethylphthalate	10	--	--	10 U	10 U	10 U	10 U	0.3 J	0.5 J	10 U	0.3 U

Notes:

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = compound not detected above concentration listed

J = compound detected, but below contract required  
quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

\* - Monitoring Well MW-S1 did not contain sufficient water  
to sample for phthalates.

PAL Exceedance - 

ES Exceedance - 



**Table 5A**  
**Phthalate Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte, $\mu\text{g/l}$	CRQL	NR140 PAL	NR140 ES	MW-13S (dupe)		MW-14S	MW-15D	MW-15S	MW-19D	MW-19S
				MW-13S (dupe)	Reanalysis					
bis(2-Ethylhexyl)Phthalate	10	0.6	6	0.9 U	1 U	0.8 U	9 U	2 U	2 U	0.5 U
Di-n-Butylphthalate	10	--	--	0.2 U	0.3 U	0.5 U	1 U	1 U	0.6 U	0.5 U
Diethylphthalate	10	--	--	10 U	0.3 J	10 U	10 U	0.7 U	10 U	10 U

**Notes:**

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = compound not detected above concentration listed

J = compound detected, but below contract required  
quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

\* - Monitoring Well MW-S1 did not contain sufficient water  
to sample for phthalates.

PAL Exceedance - 

ES Exceedance - 

**Table 5A**  
**Phthalate Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte, $\mu\text{g/l}$	CRQL	NR140 PAL	NR140 ES	MW-19S (dupe)	MW-20S	MW-S1*	MW-S1A	MW-S1AR	MW-S2	MW-S2A	MW-S2AR
bis(2-Ethylhexyl)Phthalate	10	0.6	6	0.9 U	0.9 U		6 U	5 U	6 U	2 U	2 U
Di-n-Butylphthalate	10	--	--	0.6 U	0.5 U		0.7 U	0.7 U	0.6 U	0.5 U	2 U
Diethylphthalate	10	--	--	10 U	10 U		0.6 J	2 J	10 U	10 U	0.2 J

Notes:

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = compound not detected above concentration listed

J = compound detected, but below contract required  
quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

\* - Monitoring Well MW-S1 did not contain sufficient water  
to sample for phthalates.

PAL Exceedance -

ES Exceedance -

**Table 5A**  
**Phthalate Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

	CRQL	NR140 PAL	NR140 ES	MW-S3	MW-S3A	MW-S3A (dupe)	MW-S3AR	MW-FB02	MW-FB03	MW-FB01
<u>Analyte, <math>\mu\text{g/l}</math></u>										
bis(2-Ethylhexyl)Phthalate	10	0.6	6	8 U	5 U	7 U	26 B	0.8 BJ	2 BJ	10 U
Di-n-Butylphthalate	10	--	--	0.5 U	0.5 U	0.9 U	0.7 U	0.7 BJ	0.7 J	10 U
Diethylphthalate	10	--	--	0.5 J	0.5 J	0.6 J	0.6 J	10 U	10 U	10 U

Notes:

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = compound not detected above concentration listed

J = compound detected, but below contract required  
quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

\* - Monitoring Well MW-S1 did not contain sufficient water  
to sample for phthalates.

PAL Exceedance - [REDACTED]

ES Exceedance - [REDACTED]

**Table 5A**  
**Phthalate Concentrations**  
**Groundwater Monitoring Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

Analyte, $\mu\text{g/l}$	CRQL	NR140 PAL	NR140 ES	Method Blank 10	Method Blank 12	Method Blank 18	Method Blank 38
bis(2-Ethylhexyl)Phthalate	10	0.6	6	2 J	2 J	2 J	4 J
Di-n-Butylphthalate	10	--	--	0.5 J	0.9 J	10 U	0.5 J
Diethylphthalate	10	--	--	0.3 J	10 U	10 U	10 U

Notes:

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = compound not detected above concentration listed

J = compound detected, but below contract required  
quantitation limit

-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

\* - Monitoring Well MW-S1 did not contain sufficient water  
to sample for phthalates.

PAL Exceedance -

ES Exceedance -

**Table 5B**  
**Phthalate Concentrations**  
**Residential Wells**  
**Round 1 Long Term Groundwater Monitoring**  
**Spickler Landfill Site**  
**STS Project No. 84374XA**

<u>Analyte, <math>\mu\text{g/l}</math></u>	<u>CRQL</u>	<u>NR140 PAL</u>	<u>NR140 ES</u>	<u>RW-2543</u>	<u>RW-2543 (dupe)</u>	<u>RW-2551</u>	<u>RW-FB01</u>
bis(2-Ethylhexyl)Phthalate	10	0.6	6	10 U	0.6 U	2 U	3 U
Di-n-Butylphthalate	10	--	--	0.5 U	0.4 U	0.6 U	0.5 U
Diethylphthalate	10	--	--	10 U	10 U	10 U	10 U

Notes:

Samples collected in March 1996

Units in  $\mu\text{g/L}$

U = compound not detected above concentration listed


-- = No NR140 ES or PAL established

CRQL - Contract Required Quantitation Limit

ES Exceedance - XXXXXXXXXX

STS

## APPENDIX




## **LIST OF APPENDICES**

Appendix A - Field Sampling Sheets  
Appendix B - Chain-of-Custody Forms  
Appendix C - HES Case Narrative

STS

A





## **APPENDIX A**

### **Field Sampling Sheets**

Project <u>Spickler LF</u>		Project No. <u>84374xA</u>
Location <u>Spencer WI</u>		Day/Date <u>Mon 3/11/96</u>
Contractor _____		Weather/Temp. <u>30's</u>
		Client <u>Weyerhaeuser</u>
Equipment _____	Arrive Job <u>10:00</u>	TOTAL CHARGEABLE HOURS <div style="border: 1px solid black; padding: 10px; display: inline-block;">11.5</div>
Rental _____	Depart Job <u>4:30</u>	
Tolls \$ _____	Total Hours on Job <u>6.5</u>	
Parking \$ _____	Lab Time <u>1.0</u>	
Mileage _____	Travel Time <u>4.0</u>	

Summary of Technical and/or Engineering Services Performed, Including Field Test Data. Locations, Elevations and Depths are Estimated.

Collected water levels from all wells on site except for wells S-1 & S1A which were not located. Water levels from all leachate head wells on site. Depth to water and depth to well bottom were recorded with a water level indicator. Well PVC stickler was not measured due to snow cover.

Gas levels were monitored in 10 GAS probes at wells BS, GS, S-3. Well S-1 was not located. Concentrations of % CH<sub>4</sub>, CO<sub>2</sub> were measured with GA-90 Infrared gas detector.

☐ Field Test Data is Estimated  
Pending Final Laboratory Test Results.

Site Sketch: Indicate North

Field Representative \_\_\_\_\_

Position \_\_\_\_\_

Company \_\_\_\_\_

By David M. Kern

STS Consultants, Ltd.

2 WHITE OFFICE • YELLOW TIME CARD • WHITE FIELD



Spickler

## WATER LEVEL DATA SHEET

Project: Spickler LFProject No.: 84374XA  
85894XHObserver: DMWeather: 30 S overcastDate: 3/11/96Type Water Level Indicator Used: Slope Indicator I.D. No: 13088

Well/Plaz. Number	Clock Time	Casing Stick-Up (ft)	Casing Top Elev. (ft)	Depth To Water (ft)	Depth To Bottom (ft)	Water Elev. (ft)	Remarks
20 S		N/A Snow cover		5.43	21.72		
14 D		N/A Snow cover		17.29	62.25		
14 S		N/A Snow cover		11.71	26.19		
15 S		N/A Snow cover		14.28	27.45		
15 D		N/A Snow cover		20.54	72.73		
18 S		N/A Snow cover		14.40	26.36		
6 S		N/A Snow cover		13.88	28.14		
6 D		N/A Snow cover		18.32	62.75		
12 D		N/A Snow cover		19.43	62.45		
12 S		N/A Snow cover		12.54	27.70		
16 S		N/A Snow cover		5.28	20.90		
11 S		N/A Snow cover		8.08	20.54		
8 S		N/A Snow cover		12.12	22.52		
8 D		N/A Snow cover		32.82	47.65		
7 D		N/A Snow cover		29.28	62.30		
7 S		N/A Snow cover		20.16	24.09		
10 D		N/A Snow cover		32.99	62.50		
10 S		N/A Snow cover		6.78	20.70		

Note reference point used if not top of PVC riser casing:

Additional Remarks:



Project No. 84374 XA

Project Spickler LF Day/Date Tues 3/12/96

Location Spencer WI Weather/Temp. 50's ptly. cloudy

Contractor \_\_\_\_\_ Client Weyerhaeuser

Equipment _____	Arrive Job <u>7:00</u>	TOTAL CHARGEABLE HOURS <div style="border: 1px solid black; padding: 5px; display: inline-block;">10.5</div>
Rental _____	Depart Job <u>5:30</u>	
Tolls \$ _____	Total Hours on Job <u>10.5</u>	
Parking \$ _____	Lab Time <u>—</u>	
Mileage _____	Travel Time <u>—</u>	

Summary of Technical and/or Engineering Services Performed, including Field Test Data. Locations, Elevations and Depths are Estimated.

Purged & Sampled the following wells: 20S, 14S, 15S, 13S + Dupe  
13D, 15D, 6S, 19D, 19S + Dupe, FB01.

Disposable Bailers were used to purge four well volumes from each well. Well 19D Bailed Dry and was let to recharge prior to sampling. At each site 3-40 ml HCl vials, 2-l Amber naphres, 1-l HNO<sub>3</sub> filtered, 1-l NaOH were collected. FB01 was complete with store bought Distilled water.

All purge water was disposed of into leachate collection system. pH, cond & Temperature was measured and recorded in field book along with observations of color, odor & turbidity.

Samples were stored on ice after collection.  
E & E oversight representative on site.

☐ Field Test Data is Estimated  
Pending Final Laboratory Test Results.

Site Sketch: Indicate North

Field Representative \_\_\_\_\_

Position \_\_\_\_\_

Company \_\_\_\_\_

By D. Makel?  
STS Consultants, Ltd.

2 WHITE OFFICE • YELLOW TIME CARD • WHITE FIELD

# SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler LF  
Location: Spencer WI  
Well Number: 20 S  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374 x A  
Tester: OCM  
Date Sampled: 3/12/96

## GENERAL CONDITIONS:

Surface Seal: OK N/A Snow cover Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged Missing: \_\_\_\_\_  
Well Cap: OK Damaged Missing: If Missing Replaced?  
Temperature: \_\_\_\_\_ Clear/Cloudy/Rain

## WELL DATA:

Measuring Device: M scope  
Stick Up or Down: N/A (Snow covered) (from Ground Surface)  
Depth to Water: 5.43 (from TPVC)  
Depth to Bottom: 21.72 (from TPVC)  
Length of Water: 16.29  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## PURGING/SAMPLING:

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Bailer Sampling Device: Disposable Bailer  
Volume Required: 30  
Volume Purged: 30 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes (no)

Purging - Time Start: 7:55 Time Ended: 8:36  
Total Time Spent Purging: 41 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## IN-SITU TESTING:

Turbidity: clear (turbid) opaque

Odor: none

Color: light Brown

pH: 6.05 @ 6.0 °C

Uncorrected Conductivity: 119 x 1

Water Temp. (from Cond.) 6.1

Comments \_\_\_\_\_

## Samples Collected

VOCs- 3-40 ml #/Size Hel Preservatives

Metals- 1-2 HNO3

Indicator Parameters NONE 2-

Indicator Parameters 1-2 NaOH

Corrected Cond 191 umohs/cm

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler LF  
Location: Spencer WI  
Well Number: 145  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374XA  
Tester: DCM  
Date Sampled: 3/2/96

## **GENERAL CONDITIONS:**

Surface Seal: N/A OK Snow cover Damaged  
Protector Pipe: OK Damaged  
Well Cap: OK Damaged  
Temperature: 30's - 40

Missing: \_\_\_\_\_  
Missing: \_\_\_\_\_  
Missing: If Missing Replaced?  
Clear/Cloudy/Rain Cloudy

## **WELL DATA:**

Measuring Device: M Scope  
Stick Up or Down: N/A Snow covered (from Ground Surface)  
Depth to Water: 11.71 (from TPVC)  
Depth to Bottom: 26.91 (from TPVC)  
Length of Water: 15.20  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes:  $[(\text{length of water} \times 0.12) + 0.08] \times 29.9$  For 2" well  
10 Well Volumes:  $[(\text{length of water} \times 0.12) + 0.08] \times 74.8$  For 2" well

Purging Device: Disposable Bailer Sampling Device: Disposable Bailer  
Volume Required: 30 gallons  
Volume Purged: 30 gallons Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 8:45 Time Ended: 9:30  
Total Time Spent Purging: 45 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: clear turbid opaque  
Odor: none  
Color: light Brown  
pH: 6.19 @ 7.5 °C  
Uncorrected Conductivity: 70 x 1  
Water Temp. (from Cond.) 7.9  
Comments: \_\_\_\_\_

Samples Collected		Preservatives
	#/Size	
VOCs-	<u>3-40 ml</u>	<u>He1</u>
Metals-	<u>1-2</u>	<u>MN03</u>
Indicator Parameters		<u>NONE 2-2</u>
Indicator Parameters		<u>1-2 NaOH</u>

106 Corrected Cond unhol/cm

# SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer WI  
Well Number: 155  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374XA  
Tester: DCM  
Date Sampled: 3/12/96

## GENERAL CONDITIONS:

Surface Seal: OK Snow cover  
Protector Pipe: OK Damaged  
Well Cap: OK Damaged  
Temperature: 40 Damaged

Missing: \_\_\_\_\_  
Missing: \_\_\_\_\_  
Missing: If Missing Replaced?  
Clear Cloudy Rain

## WELL DATA:

Measuring Device: m Scope  
Stick Up or Down: N/A (Snow cover) (from Ground Surface)  
Depth to Water: 14.28 (from TPVC)  
Depth to Bottom: 27.45 (from TPVC)  
Length of Water: 13.17  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## PURGING/SAMPLING:

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable Bailer  
Volume Required: 26 gallons  
Volume Purged: 26 gallons Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 9:28 Time Ended: 10:05  
Total Time Spent Purging: 30 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## IN-SITU TESTING:

Turbidity: clear turbid opaque  
Odor: none  
Color: light Red  
pH: 6.26 @ 6.7 °C  
Uncorrected Conductivity: 99 x 1  
Water Temp. (from Cond.) 7.0  
Comments \_\_\_\_\_

Samples Collected  
#/Size  
VOCs- 360mc Preservatives Hel  
Metals- 1-e HNO3  
Indicator Parameters NONE 2-e  
Indicator Parameters 1-e NaOH

Corrected Cond 155 umhos/cm



# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler LF  
Location: Spencer WI  
Well Number: 135 + Dye  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374xA  
Tester: OLM  
Date Sampled: 3/12/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Snow cover Damaged  
Protector Pipe: OK Damaged  
Well Cap: OK Damaged  
Temperature: 40  
Missing: \_\_\_\_\_  
Missing: \_\_\_\_\_  
Missing: If Missing Replaced?  
Clear Cloudy / Rain

## **WELL DATA:**

Measuring Device: mscope  
Stick Up or Down: N/A Snow cover (from Ground Surface)  
Depth to Water: 11.48 (from TPVC)  
Depth to Bottom: 23.50 (from TPVC)  
Length of Water: 12.02  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: 24  
Volume Purged: 25 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 10:45 Time Ended: 11:25  
Total Time Spent Purging: 40 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: clear turbid opaque  
Odor: Slight Teachick/organic?  
Color: light Gray  
pH: 6.19 @ 9.4 °C  
Uncorrected Conductivity: 228 x 1  
Water Temp. (from Cond.) 9.9  
Comments: corrected cond 327 uenals/cm

Samples Collected  
VOCs- 3-40 ml #/Size  
Metals- 1-2  
Indicator Parameters  
Indicator Parameters

Preservatives  
HCl  
HNO<sub>3</sub>  
NONE 2-2  
1-2 NaOH

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer WI  
Well Number: 13D  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374XA  
Tester: DLM  
Date Sampled: 3/12/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Snow cover Damaged Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged Missing: \_\_\_\_\_  
Well Cap: OK Damaged Missing: If Missing Replaced?  
Temperature: 40 Clear Cloudy/Rain

## **WELL DATA:**

Measuring Device: m Scope  
Stick Up or Down: NA Snow cover (from Ground Surface)  
Depth to Water: 16.42 (from TPVC)  
Depth to Bottom: 62.75 (from TPVC)  
Length of Water: 46.33  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable Bail  
Volume Required: 25 gallons  
Volume Purged: 25 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 10:45 Time Ended: 11:45  
Total Time Spent Purging: 1 hr

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: <u>clear</u> turbid opaque	Samples Collected	Preservatives
Odor: <u>none</u>	VOCs- <u>3-40 ml</u>	<u>14ml</u>
Color: <u>clear</u>	Metals- <u>1-2</u>	<u>14ml</u>
pH: <u>6.57 @ 9.3</u> °C	Indicator Parameters	<u>NONE 2-2</u>
Uncorrected Conductivity: <u>29 x 1</u>	Indicator Parameters	<u>1-2 NaOH</u>
Water Temp. (from Cond.) <u>9.1</u>		
Comments: <u>Corrected Cond 29 umhos/cm</u>		

Fill out the entire form.  
If it does not apply  
mark N/A

## SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET

Project Name: Spickler LF  
Location: Spencer WI  
Well Number: 150  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374xA  
Tester: DCM  
Date Sampled: 3/12/96

### GENERAL CONDITIONS:

Surface Seal: OK Snow Cover Damaged  
Protector Pipe: OK Damaged  
Well Cap: OK Damaged  
Temperature: 40

Missing: \_\_\_\_\_  
Missing: \_\_\_\_\_  
Missing: if Missing Replaced?  
Clear/Cloudy/Rain

### WELL DATA:

Measuring Device: M Scope  
Stick Up or Down: N/A Snow Cover (from Ground Surface)  
Depth to Water: 20.54 (from TPVC)  
Depth to Bottom: 72.73 (from TPVC)  
Length of Water: 52.19  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

### PURGING/SAMPLING:

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable Bailer  
Volume Required: 25 gallons  
Volume Purged: 25 gallons Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 10:40 Time Ended: 10:52  
Total Time Spent Purging: 50 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

### IN-SITU TESTING:

Turbidity: Clear turbid opaque  
Odor: none  
Color: Clear  
pH: 6.60 @ 9.8 °C  
Uncorrected Conductivity: 23 x1  
Water Temp. (from Cond.) 10.0  
Comments \_\_\_\_\_

Samples Collected		Preservatives
	#/Size	
VOCs-	<u>3-40 ml</u>	<u>HCl</u>
Metals-	<u>1-L</u>	<u>HNO3</u>
Indicator Parameters		<u>NONE 2-L</u>
Indicator Parameters		<u>1-L NaOH</u>

corrected Cond 33 umhos/cm

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: 65  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374XA  
Tester: DCM  
Date Sampled: 3/12/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Snow cover Damaged  
Protector Pipe: OK Damaged  
Well Cap: OK Damaged  
Temperature: 40'S  
Missing: \_\_\_\_\_  
Missing: \_\_\_\_\_  
Missing: If Missing Replaced?  
Clear/Cloudy/Rain

## **WELL DATA:**

Measuring Device: mScope  
Stick Up or Down: N/A Snow cover (from Ground Surface)  
Depth to Water: 13.88 (from TPVC)  
Depth to Bottom: 28.14 (from TPVC)  
Length of Water: 14.26  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: 27  
Volume Purged: 27 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 14:45 Time Ended: 15:20  
Total Time Spent Purging: 35 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: <u>clear</u> <u>turbid</u> opaque	Samples Collected	Preservatives
Odor: <u>none</u>	#/Size	
Color: <u>light Gray / Brown</u>	VOCs- <u>3-40 m</u>	<u>H<sub>2</sub>O</u>
pH: <u>5.40 @ 38.4</u> °C	Metals- <u>1-2</u>	<u>HNO<sub>3</sub></u>
Uncorrected Conductivity: <u>149 x 10</u>	Indicator Parameters	<u>NONE 2-e</u>
Water Temp. (from Cond.) <u>8.9</u>	Indicator Parameters	<u>1-e N<sub>2</sub>O<sub>4</sub></u>
Comments: <u>220 corrected cond umhos/cm</u>		

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler LF  
Location: Spencer WI  
Well Number: 195 + Dope  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374xA  
Tester: Dum  
Date Sampled: 3/12/96

## **GENERAL CONDITIONS:**

Surface Seal: OK <sup>Snow cover</sup> Damaged Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged Missing: \_\_\_\_\_  
Well Cap: OK Damaged Missing: If Missing Replaced?  
Temperature: \_\_\_\_\_ 40 Clear Cloudy Rain

## **WELL DATA:**

Measuring Device: M Scope  
Stick Up or Down: N/A Snow cover (from Ground Surface)  
Depth to Water: 8.01 (from TPVC)  
Depth to Bottom: 21.10 (from TPVC)  
Length of Water: 13.09  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.08] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.08] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable Bail  
Volume Required: 25  
Volume Purged: 25 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 14:25 Time Ended: 15:00  
Total Time Spent Purging: 45 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: clear turbid opaque Samples Collected  
Odor: leachate #/Size  
Color: light grey VOCs- 3-40 ml Preservatives  
pH: 6.13 @ 10.6 °C Metals- 1.2 HNO3  
Uncorrected Conductivity: 62 x 10 um Indicator Parameters NONE 2-2  
Water Temp. (from Cond.) 11.0 Indicator Parameters 1-2 260H  
Comments 861 corrected conc umhos/cm

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler LF  
Location: Spencer wt  
Well Number: 19 D  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374xA  
Tester: DLM  
Date Sampled: 3/12/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Snow cover Damaged \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_  
Temperature: 40 \_\_\_\_\_  
Missing: \_\_\_\_\_  
Missing: \_\_\_\_\_  
Missing: If Missing Replaced?  
Clear Cloudy Rain

## **WELL DATA:**

Measuring Device: m scope  
Suck Up or Down: N/A Snow cover (from Ground Surface)  
Depth to Water: 35.98 (from TPVC)  
Depth to Bottom: 52.05 (from TPVC)  
Length of Water: 16.07  
Free Product Observed: yes/OK Thickness: N/A (in bailer/by 1-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes:  $[(\text{length of water} \times 0.12) + 0.06] \times 29.9$  For 2" well  
10 Well Volumes:  $[(\text{length of water} \times 0.12) + 0.06] \times 74.8$  For 2" well

Purging Device: Disposable Sampling Device: Disposable Bailer  
Volume Required: 20  
Volume Purged: 13 gallons Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 14:25 Time Ended: 15:15  
Total Time Spent Purging: 30 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: clear turbid opaque  
Odor: none  
Color: light Brown  
pH: 5.48 @ 10.5 °C  
Uncorrected Conductivity: 53 x 1  
Water Temp. (from Cond.): 11.0  
Comments: \_\_\_\_\_

Samples Collected		Preservatives
	#/Size	
VOCs-	<u>3-40 ml</u>	<u>HCl</u>
Metals-	<u>1-L</u>	<u>HNO3</u>
Indicator Parameters		<u>NONE 2-L</u>
Indicator Parameters		<u>1-L NaOH</u>

Corrected Cond 74 umhos/cm

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler LF  
Location: Spencer WE  
Well Number: FB01  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374XA  
Tester: DLM  
Date Sampled: 3/12/96

## **GENERAL CONDITIONS:**

Surface Seal: OK N/A Sealed N/A Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged Missing: \_\_\_\_\_  
Well Cap: OK Damaged Missing: If Missing Replaced?  
Temperature: 40's Clear/Cloudy/Rain: Clear

## **WELL DATA:**

Measuring Device: N/A  
Stick Up or Down: \_\_\_\_\_ (from Ground Surface)  
Depth to Water: \_\_\_\_\_ (from TPVC)  
Depth to Bottom: \_\_\_\_\_ (from TPVC)  
Length of Water: \_\_\_\_\_  
Free Product Observed: yes/no Thickness: \_\_\_\_\_ (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes:  $[(\text{length of water} \times 0.12) + 0.08] \times 29.9$  For 2" well  
10 Well Volumes:  $[(\text{length of water} \times 0.12) + 0.08] \times 74.8$  For 2" well

N/A  
Purging Device: \_\_\_\_\_ Sampling Device: \_\_\_\_\_  
Volume Required: \_\_\_\_\_  
Volume Purged: \_\_\_\_\_ Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: \_\_\_\_\_ Time Ended: \_\_\_\_\_  
Total Time Spent Purging: \_\_\_\_\_

Decon Method: Cleaned in office/Field Decon Method: \_\_\_\_\_

## **IN-SITU TESTING:**

Turbidity: <u>clear</u> turbid opaque	Samples Collected	Preservatives
Odor: <u>none</u>	#/Size	HCl
Color: <u>clear</u>	VOCs- <u>3-40 ml</u>	HNO3
pH: <u>6.60 @ 12.9</u> °C	Metals- <u>1-2</u>	NONE <u>2-2</u>
Uncorrected Conductivity: <u>4 x 1</u>	Indicator Parameters	<u>1-2 NaOH</u>
Water Temp. (from Cond.) <u>13.0</u>	Indicator Parameters	
Comments: <u>corrected cond 5 umhos/cm</u>		

STS Geo-Environmental Group  
Field Report



Project Spickler LF Project No. 84374XA  
Location Spencer WI Day/Date 3/13/96 Wed  
Contractor \_\_\_\_\_ Weather/Temp. 50's Clear  
Client Veyerhaeuser  
Equipment \_\_\_\_\_ Arrive Job 7:00  
Rental \_\_\_\_\_ Depart Job 5:30  
Tolls \$ \_\_\_\_\_ Total Hours 10.5  
Parking \$ \_\_\_\_\_ on Job  
Mileage \_\_\_\_\_ Lab Time \_\_\_\_\_  
Travel Time \_\_\_\_\_

TOTAL CHARGEABLE HOURS 10.5

Summary of Technical and/or Engineering Services Performed, including Field Test Data. Locations, Elevations and Depths are Estimated.

Completed Wells: 11S, 6D, 7S, 7D, 10S, FB02,  
RW 2543, 2543 Dure, 2551 RW FB01  
Monitoring wells were purged and sampled with Disposable Bailers.  
Four well volumes were removed unless the well bailed dry. Wells  
that bailed dry were let to recharge prior to sampling. AT  
each site 3-40 ml H<sub>2</sub>O vials, 2-2 Amber no pres, 1-2 HNO<sub>3</sub> &  
1-2 NaOH were collected. Metal S Sample (HNO<sub>3</sub>) were filtered.  
pH, Cond & Temp. were measured and recorded in field book  
along with observations of color odor & turbidity.  
Well purge water contained in leachate collection system.  
4 coolers shipped to Hazelton via Dunham Express.

Attempted to locate wells SI & SIA - wells not found.  
Recorded Panel readings from leachate collection system main  
Panel at lift station 1 & 2.

☐ Field Test Data is Estimated  
Pending Final Laboratory Test Results.

Site Sketch: Indicate North

Field Representative \_\_\_\_\_  
Position \_\_\_\_\_  
Company \_\_\_\_\_

By D. Makler  
STS Consultants, Ltd.

2 WHITE OFFICE • YELLOW TIME CARD • WHITE FIELD



# SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler LF  
Location: Spencer WE  
Well Number: F302  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374 x D  
Tester: Dum  
Date Sampled: 3/13/96

## GENERAL CONDITIONS:

N/A

Surface Seal:	OK	Damaged	Missing: _____
Protector Pipe:	OK	Damaged	Missing: _____
Well Cap:	OK	Damaged	Missing: If Missing Replaced?
Temperature: _____			Clear/Cloudy/Rain

## WELL DATA:

N/A

Measuring Device: \_\_\_\_\_  
Stick Up or Down: \_\_\_\_\_ (from Ground Surface)  
Depth to Water: \_\_\_\_\_ (from TPVC)  
Depth to Bottom: \_\_\_\_\_ (from TPVC)  
Length of Water: \_\_\_\_\_  
Free Product Observed: yes/no Thickness: \_\_\_\_\_ (in bailer/by I-Probe)

## PURGING/SAMPLING:

Well Purging Calculations: 4 Well Volumes:  $[(\text{length of water} \times 0.12) + 0.08] \times 29.9$  For 2" well  
10 Well Volumes:  $[(\text{length of water} \times 0.12) + 0.08] \times 74.8$  For 2" well

N/A

Purging Device: \_\_\_\_\_ Sampling Device: \_\_\_\_\_  
Volume Required: \_\_\_\_\_  
Volume Purged: \_\_\_\_\_ Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: \_\_\_\_\_ Time Ended: \_\_\_\_\_  
Total Time Spent Purging: \_\_\_\_\_

Decon Method: Cleaned in office/Field Decon Method: \_\_\_\_\_

## IN-SITU TESTING:

Turbidity: clear turbid opaque  
Odor: none  
Color: clear  
pH: 6.39 @ 13.2 °C  
Uncorrected Conductivity: 2 x 1  
Water Temp. (from Cond.) 13.1  
Comments \_\_\_\_\_

Samples Collected		Preservatives
	#/Size	
VOCs-	<u>3-40 ml</u>	<u>Hcl</u>
Metals-	<u>1-2</u>	<u>None?</u>
Indicator Parameters		<u>NONE 2-2</u>
Indicator Parameters		<u>1-e no ch</u>

corrected cond 3 umho/cm

# SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler LF  
Location: Spencer  
Well Number: 70  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374 xA  
Tester: Dem  
Date Sampled: 3/13/96

## GENERAL CONDITIONS:

Surface Seal: OK Snow Cover Damaged Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged Missing: \_\_\_\_\_  
Well Cap: OK Damaged Missing: If Missing Replaced?  
Temperature: 40's Clear/Cloudy/Rain

## WELL DATA:

Measuring Device: m Scope  
Stick Up or Down: N/A Snow Cover (from Ground Surface)  
Depth to Water: 29.28 (from TPVC)  
Depth to Bottom: 62.30 (from TPVC)  
Length of Water: 33.02  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## PURGING/SAMPLING:

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: 25  
Volume Purged: 25 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes (no)

Purging - Time Start: 10:05 Time Ended: 10:50  
Total Time Spent Purging: 45 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## IN-SITU TESTING:

Turbidity: clear turbid opaque  
Odor: none  
Color: clear  
pH: 5.87 @ 10.2 °C  
Uncorrected Conductivity: 29 x 1  
Water Temp. (from Cond.) 10.3  
Comments \_\_\_\_\_

Samples Collected		Preservatives
	#/Size	
VOCs-	<u>3-40 ml</u>	<u>HCl</u>
Metals-	<u>1-2</u>	<u>HNO<sub>3</sub></u>
Indicator Parameters		<u>NONE 2-2</u>
Indicator Parameters		<u>1-2 neoh</u>

41 corrected Cond ughos/cm

# SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer WS  
Well Number: 105  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374xA  
Tester: DLm  
Date Sampled: 3/13/96

## GENERAL CONDITIONS:

Surface Seal: OK <sup>Snow cover</sup> Damaged Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged Missing: \_\_\_\_\_  
Well Cap: OK Damaged Missing: If Missing Replaced?  
Temperature: 40 Clear Cloudy/Rain

## WELL DATA:

Measuring Device: M Scope  
Stick Up or Down: N/A Snow cover (from Ground Surface)  
Depth to Water: 6.78 (from TPVC)  
Depth to Bottom: 20.70 (from TPVC)  
Length of Water: 13.92  
Free Product Observed: yes/NO Thickness: N/A (in bailer/by I-Probe)

## PURGING/SAMPLING:

Well Purging Calculations: 4 Well Volumes:  $(\text{length of water} \times 0.12) + 0.061 \times 29.9$  For 2" well  
10 Well Volumes:  $(\text{length of water} \times 0.12) + 0.061 \times 74.8$  For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: 28 gallons  
Volume Purged: 28 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes NO

Purging - Time Start: 8:10 Time Ended: 9:40  
Total Time Spent Purging: 1 hr 30 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## IN-SITU TESTING:

Turbidity: Clear turbid opaque  
Odor: leachate  
Color: gray  
pH: 5.93 @ 8.9 °C  
Uncorrected Conductivity: 417 x 1  
Water Temp. (from Cond.) 9.0  
Comments: \_\_\_\_\_

Samples Collected		Preservatives
	#/Size	
VOCs-	<u>3-40 mL</u>	<u>He1</u>
Metals-	<u>1-L</u>	<u>HNO3</u>
Indicator Parameters		<u>NONE 2-L</u>
Indicator Parameters		<u>1-L NaOH</u>

613 corrected conc unhas/cm  
ms/MSD Extra 6 40-mL He1 vials  
1-L HNO3  
1-L NaOH  
2-L Amber

# SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler Job No.: 84374xA  
Location: Spencer Wn Tester: Dm  
Well Number: 75 Date Sampled: 3/13/96  
Previous Well Sampled: \_\_\_\_\_

## GENERAL CONDITIONS:

Surface Seal: ~~OK~~ Snow cover Damaged Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged Missing: \_\_\_\_\_  
Well Cap: OK Damaged Missing: If Missing Replaced?  
Temperature: \_\_\_\_\_ Clear/Cloudy/Rain

## WELL DATA:

Measuring Device: M Scope  
Stick Up or Down: N/A Snow cover (from Ground Surface)  
Depth to Water: 20.16 (from TPVC)  
Depth to Bottom: 24.05 (from TPVC)  
Length of Water: 3.89  
Free Product Observed: yes ~~no~~ Thickness: N/A (in bailer/by I-Probe)

## PURGING/SAMPLING:

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: 15 gallons  
Volume Purged: 2.0 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes ~~no~~

Purging - Time Start: 10:00 Time Ended: 10:20  
Total Time Spent Purging: 20 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## IN-SITU TESTING:

Turbidity: <u>clear</u> <del>turbid</del> <u>opaque</u>	Samples Collected	
Odor: <u>B none</u>	#/Size	Preservatives
Color: <u>Brown</u>	VOCs- <u>3-40</u>	<u>MC</u>
pH: <u>5.12 @ 11.0</u> °C	Metals- <u>1-L</u>	<u>HNO3</u>
Uncorrected Conductivity: <u>99 x 1</u>	Indicator Parameters	<u>NONE 2-L</u>
Water Temp. (from Cond.) <u>11.0</u>	Indicator Parameters	<u>1-L neqH</u>
Comments _____	Corrected Cond <u>190 umhos/cm</u>	

# SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: 60  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374xA  
Tester: DLm  
Date Sampled: 3/13/96

## GENERAL CONDITIONS:

Surface Seal: OK N/A Snow cover Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged Missing: \_\_\_\_\_  
Well Cap: OK Damaged Missing: If Missing Replaced?  
Temperature: 40.5 Clear Cloudy/Rain

## WELL DATA:

Measuring Device: M Scope  
Stick Up or Down: N/A Snow cover (from Ground Surface)  
Depth to Water: 18.32 (from TPVC)  
Depth to Bottom: 62.75 (from TPVC)  
Length of Water: 44.43  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## PURGING/SAMPLING:

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Bail Sampling Device: Disposable Bail  
Volume Required: 25  
Volume Purged: 25 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 8:30 Time Ended: 10:00  
Total Time Spent Purging: 1.5 hr

Decon Method: Cleaned in office/Field Decon Method: Disposable

## IN-SITU TESTING:

Turbidity: <u>clear</u> turbid opaque	Samples Collected	
Odor: <u>none</u>	VOCs- <u>3-40 ml</u>	Preservatives <u>Hel</u>
Color: <u>clear</u>	Metals- <u>1-2</u>	<u>HNO3</u>
pH: <u>8</u> °C	Indicator Parameters <u>NONE 2-2</u>	
Uncorrected Conductivity: <u>28</u> x1	Indicator Parameters <u>1-2 NOC H</u>	
Water Temp. (from Cond.) <u>8.1</u>		
Comments _____		

42 unkos/cm corrected cond

# **SPICKLER LANDFILL SITE RESIDENTIAL WELL SAMPLING SHEET**

Fill out the entire form  
If it does not apply  
mark N/A

Project Name: Spickler LF  
Location: Spencer wt  
Well Number: 2551 + B51msd  
Previous Sampling Point: \_\_\_\_\_

Job No.: 843747A  
Tester: DM  
Date Sampled: 3/13/96

## **GENERAL CONDITIONS :**

Sampling location (ie. tap, spigot): OUT side TAP

Temperature: 50 Clear/Cloudy/Rain

## **SAMPLING :**

Sampling Device: N/A  
Volume Required: 5 min purge

Samples Collected		Preservatives
	Size	
VOCs	<u>3-40 m</u>	<u>Heptane</u>
Metals	<u>1-E</u>	<u>None</u>
Indicator Parameters		<u>None</u>
Indicator Parameters		<u>None</u>

## **IN-SITU TESTING**

Turbidity: clear turbid opaque  
Odor: none  
Color: clear  
pH: 6.60 10.5 °C:  
Uncorrected Conductivity: 84 x 10  
Liquid Temp. (from Cond.) 10.3  
Comments: \_\_\_\_\_

20 Sp ST

corrected cond 119

RWFB01 - 2.15p

# **SPICKLER LANDFILL SITE RESIDENTIAL WELL SAMPLING SHEET**

Fill out the entire f.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: 2543 + Dpe  
Previous Sampling Point: OUT Side Tap

Job No.: 84374 XA  
Tester: DLM  
Date Sampled: 5/13/96

## **GENERAL CONDITIONS :**

Sampling location (ie. tap, spigot): OUT Side TAP

Temperature: 40 S Clear Cloudy/Rain

## **SAMPLING :**

Sampling Device: NIA  
Volume Required: 5 min purge

### Samples Collected

VOCs— 3-40 m  
Metals— 1-2  
Indicator Parameters  
Indicator Parameters

### Preservatives

None  
None  
None  
NONE

ST 1:40 / 1:45 Dpe

## **IN-SITU TESTING**

Turbidity: Clear no turbid opaque

Odor: Clear

Color: 0

pH: 6.1

Uncorrected Conductivity: 10.1

Liquid Temp. (from Cond.) 10.1

Comments

Corrected 87 umhos/cm

Facility/Project Name <u>SPICKLER LANDFILL</u>	Local Grid Location of Well ft. <u>NS</u> ft. <u>EW</u>	Well Name <u>SIAR</u>
Facility License, Permit or Monitoring Number	Grid Origin Location Lat. _____ Long. _____ or St. Plane _____ ft. N. _____ ft. E.	Well Number <u>3114196</u>
Type of Well Water Table Observation Well <input type="checkbox"/> 11 Piezometer <input checked="" type="checkbox"/> 12	Section Location of Waste/Source 1/4 of _____ 1/4 of Sec. _____ T. _____ N. R. _____	Date Well Installed <u>3/14/96</u>
Distance Well Is From Waste/Source Boundary ft. _____	Location of Well Relative to Waste/Source u <input type="checkbox"/> Upgradient s <input type="checkbox"/> Sidegradient d <input type="checkbox"/> Downgradient n <input type="checkbox"/> Not Known	Well Installed By: (Person's Name and Firm) <u>Glenn Davis</u> <u>STS Consultants</u>
Is Well A Point of Enforcement Std. Application? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		

A. Protective pipe, top elevation _____ ft. MSL	1. Cap and lock? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
B. Well casing, top elevation _____ ft. MSL	2. Protective cover pipe: a. Inside diameter: _____ b. Length: _____ c. Material: _____
C. Land surface elevation _____ ft. MSL	d. Additional protection? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If yes, describe: _____
D. Surface seal, bottom _____ ft. MSL or <u>4.0</u> ft.	3. Surface seal: _____ Bentonite <input checked="" type="checkbox"/> Concrete <input type="checkbox"/> Other <input type="checkbox"/>
12. USCS classification of soil near screen: GP <input type="checkbox"/> GM <input type="checkbox"/> GC <input type="checkbox"/> GW <input type="checkbox"/> SW <input type="checkbox"/> SP <input type="checkbox"/> SM <input type="checkbox"/> SC <input type="checkbox"/> ML <input type="checkbox"/> MH <input type="checkbox"/> CL <input type="checkbox"/> CH <input type="checkbox"/> Bedrock <input checked="" type="checkbox"/>	4. Material between well casing and protective pipe: Bentonite <input checked="" type="checkbox"/> Annular space seal <input type="checkbox"/> Other <input type="checkbox"/>
13. Sieve analysis attached? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	5. Annular space seal: a. Gravel Bentonite <input checked="" type="checkbox"/> b. _____ Lbs/gal mud weight ... Bentonite sand slurry <input type="checkbox"/> c. _____ Lbs/gal mud weight ... Bentonite slurry <input type="checkbox"/> d. _____ % Bentonite ... Bentonite-cement grout <input type="checkbox"/> e. _____ Ft <sup>3</sup> volume added for any of the above
14. Drilling method used: Rotary <input checked="" type="checkbox"/> 50 Hollow Stem Auger <input type="checkbox"/> 41 Other <input type="checkbox"/>	f. How installed: _____ Tremie <input type="checkbox"/> Tremie pumped <input type="checkbox"/> Gravity <input checked="" type="checkbox"/>
15. Drilling fluid used: Water <input checked="" type="checkbox"/> 02 Air <input type="checkbox"/> 01 Drilling Mud <input type="checkbox"/> 03 None <input type="checkbox"/> 99	6. Bentonite seal: a. Bentonite granules <input type="checkbox"/> b. <input type="checkbox"/> 1/4 in. <input checked="" type="checkbox"/> 3/8 in. <input type="checkbox"/> 1/2 in. Bentonite pellets <input type="checkbox"/> c. _____ Other <input type="checkbox"/>
16. Drilling additives used? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	7. Fine sand material: Manufacturer, product name & mesh size <u>Maupac Sand Company 40/60</u> b. Volume added <u>1.3</u> ft <sup>3</sup>
Describe _____	8. Filter pack material: Manufacturer, product name and mesh size <u>Maupac Sand Company #30</u> b. Volume added <u>1.9</u> ft <sup>3</sup>
17. Source of water (attach analysis): <u>City of Marshfield</u>	9. Well casing: Flush threaded PVC schedule 40 <input checked="" type="checkbox"/> Flush threaded PVC schedule 80 <input type="checkbox"/> Other <input type="checkbox"/>
E. Bentonite seal, top _____ ft. MSL or <u>26.8</u> ft.	10. Screen material: <u>PVC</u> a. Screen type: _____ Factory cut <input checked="" type="checkbox"/> Continuous slot <input type="checkbox"/> Other <input type="checkbox"/>
F. Fine sand, top _____ ft. MSL or <u>31.8</u> ft.	b. Manufacturer <u>Timco</u> c. Slot size: _____ d. Slotted length: _____
G. Filter pack, top _____ ft. MSL or <u>33.9</u> ft.	11. Backfill material (below filter pack): _____ None <input checked="" type="checkbox"/> Other <input type="checkbox"/>
H. Screen joint, top _____ ft. MSL or <u>35.9</u> ft.	
I. Well bottom _____ ft. MSL or <u>38.9</u> ft.	
J. Filter pack, bottom _____ ft. MSL or <u>39.4</u> ft.	
K. Borehole, bottom _____ ft. MSL or <u>39.4</u> ft.	
L. Borehole, diameter <u>6.0</u> in.	
M. O.D. well casing <u>2.38</u> in.	
N. I.D. well casing <u>2.05</u> in.	

I hereby certify that the information on this form is true and correct to the best of my knowledge.

Signature George A. Bayer Firm STS Consultants

Please complete both sides of this form and return to the appropriate DNR office listed at the top of this form as required by chs. 144, 147 and 160, Wis. Stat. and ch. NR 141, Wis. Ad. Code. In accordance with ch. 144, Wis. Stat., failure to file this form may result in a forfeiture of not less than \$10, nor more than \$5000 for each day of violation. In accordance with ch. 147, Wis. Stat., failure to file this form may result in a forfeiture of not more than \$10,000 for each day of violation. NOTE: Shaded areas are for DNR use only. See instructions for more information including where the completed form should be sent.



**STS GEO-ENVIRONMENTAL GROUP**  
**FIELD REPORT**



Subject <u>Spickler LF</u>		Job No. <u>84374XA</u>
Location	Day <u>Thurs</u>	Date <u>3/14/96</u>
Client	Weather <u>40 Cloudy</u>	
Mileage <u>478 Total</u>	Arrive Job <u>7:00</u>	Total Chargeable Hours <u>10.75</u>
Expenses	Leave Job <u>1:15</u>	
	Travel Time <u>4.0 hr</u>	
	<u>5 lab</u>	

Summary of Technical and/or Engineering Services performed, including field test data, locations, elevations & estimated depths.

- Repacked Samples with Ice for Carrier Pickup.
- Checked leachate collection System operation. Lift Station #1 would not pump into collection Tanks. Town & Country Electric on site.
- Located wells SI & SIA and collected Water levels.
- Dropped off extra equipment AT mid-states.
- Returned to STS.

Field Test Data is Estimated Pending Final Laboratory Results.

584/cpro gray ask

By:

D. Maki  
 STS Consultants, Ltd.

Route to: Solid Waste ☐ Haz. Waste ☐ Wastewater ☐  
Env. Response & Repair ☐ Underground Tanks ☐ Other ☐

Facility/Project Name <u>SICKLER LANDFILL</u>	County Name	Well Name <u>SIAR</u>
Facility License, Permit or Monitoring Number	County Code	WIS Unique Well Number
		DNR Well Number

1. Can this well be purged dry? ☐ Yes ☒ No

2. Well development method

- surged with bailer and bailed ☒ 41  
 surged with bailer and pumped ☐ 61  
 surged with block and bailed ☐ 42  
 surged with block and pumped ☐ 62  
 surged with block, bailed and pumped ☐ 70  
 compressed air ☐ 20  
 bailed only ☐ 10  
 pumped only ☐ 51  
 pumped slowly ☐ 50  
 Other ☐

3. Time spent developing well 65 min.

4. Depth of well (from top of well casing) 41.9 ft.

5. Inside diameter of well 2.05 in.

6. Volume of water in filter pack and well casing 2.1 gal.

7. Volume of water removed from well 21.5 gal.

8. Volume of water added (if any)        gal.

9. Source of water added       

10. Analysis performed on water added? ☐ Yes ☐ No  
(If yes, attach results)

11. Depth to Water  
(from top of well casing)

Before Development	After Development
<u>32.2</u> ft.	<u>40.60</u> ft.

Date 3/16/95  
m m d d y y

Time 6:25 ☒ a.m. ☐ p.m. 3:15 ☐ a.m. ☒ p.m.

12. Sediment in well bottom 1.0 inches        inches

13. Water clarity  
Clear ☐ 10  
Turbid ☒ 15  
(Describe) light brown opaque

Clear ☐ 20  
Turbid ☒ 25  
(Describe) light gray cloudy

Fill in if drilling fluids were used and well is at solid waste facility:

14. Total suspended solids 688.0 mg/l 95.0 mg/l

15. COD 61.5 mg/l 52.0 mg/l

16. Additional comments on development:

Borehole diameter 6"  
3 feet stickup

Well developed by: Person's Name and Firm

Name: George J. Bayer

Firm: STS Consultants

I hereby certify that the above information is true and correct to the best of my knowledge.

Signature: George J. Bayer

Print Initials: GJB

Firm: STS Consultants

**STS GEO-ENVIRONMENTAL GROUP**  
**FIELD REPORT**



		<b>Job No.</b>	84374xA
<b>Project</b>	Spickler LF	<b>Day</b>	Thurs
<b>Location</b>	Town of Spencer	<b>Date</b>	3/21/96
<b>Client</b>	Weyerhaeuser	<b>Weather</b>	30 clear
<b>Mileage</b>	_____	<b>Arrive Job</b>	7:00
<b>Expenses</b>	_____	<b>Leave Job</b>	7:00
		<b>Travel Time</b>	—
		<b>Total Chargeable Hours</b>	12

Summary of Technical and/or Engineering Services performed, including field test data, locations, elevations & estimated depths.

Completed wells: S3, S3A, S3AR, S1, S1A, S1AR. Newly installed wells (S3AR & S1AR) were developed with a bailer by surging and purging the well then removing 10 well volumes. TSS & CO<sub>2</sub> samples collected before and after development. Development forms attached.

Well S2AR was developed by removing 10 well volumes. The water produced before and after was light brown or tan in color. Wells S2 & S2A were also producing brown or tan sandy water. Water used to core well 2AR is assumed to have affected wells S2 & S2A. All three wells (S2, S2A & S2AR) were sampled but were not sent to the lab. Additional supplies to redevelop the wells have been sent from Milw office. Development water contained in leachate collection system.

Field Blank FB03 completed w/ store bought water, poured through a new disposable Bailer & Trained as sample.

pH, cond & Temp. Measured and recorded in Field logbook and on Field Sampling sheets. Sample color, odor & Turbidity was noted on Field Sampling sheets.

Field Test Data is Estimated Pending Final Laboratory Results.

12/16/94/apro gray ask

By:

D. Mohr  
 STS Consultants, Ltd.

Route to: Solid Waste ☐ Haz. Waste ☐ Wastewater ☐  
Env. Response & Repair ☐ Underground Tanks ☐ Other ☐

Facility/Project Name <u>Spickler</u>	County Name	Well Name <u>S-2AR</u>
Facility License, Permit or Monitoring Number	County Code	Wis. Unique Well Number
		DNR Well Number

1. Can this well be purged dry? ☐ Yes ☒ No

2. Well development method

- surged with bailer and bailed ☒ 41  
 surged with bailer and pumped ☐ 61  
 surged with block and bailed ☐ 42  
 surged with block and pumped ☐ 62  
 surged with block, bailed and pumped ☐ 70  
 compressed air ☐ 20  
 bailed only ☐ 10  
 pumped only ☐ 51  
 pumped slowly ☐ 50  
 Other ☐

3. Time spent developing well 75 min.

4. Depth of well (from top of well casing) 30.8 ft.

5. Inside diameter of well 2.06 in.

6. Volume of water in filter pack and well casing 4.0 gal.

7. Volume of water removed from well 40.0 gal.

8. Volume of water added (if any) 0.0 gal.

9. Source of water added NIA

10. Analysis performed on water added? ☒ Yes ☐ No  
(If yes, attach results)

16. Additional comments on development:

	Before Development	After Development
11. Depth to Water (from top of well casing)	<u>18.99</u> ft.	<u>22.00</u> ft.
Date	<u>03/21/96</u> m m d d y y	<u>03/21/96</u> m m d d y y
Time	<u>11:00</u> a.m. p.m.	<u>12:15</u> a.m. p.m.
12. Sediment in well bottom	<u>4.0</u> inches	<u>0.0</u> inches
13. Water clarity	Clear <input type="checkbox"/> 10 Turbid <input checked="" type="checkbox"/> 15 (Describe)	Clear <input type="checkbox"/> 20 Turbid <input checked="" type="checkbox"/> 25 (Describe)
Fill in if drilling fluids were used and well is at solid waste facility:		
14. Total suspended solids	<u>0.1</u> mg/l <u>33.0</u>	<u>33.0</u> mg/l
15. COD	<u>19.1</u> mg/l	<u>5.0</u> mg/l

Well developed by: Person's Name and Firm

Name: Gene Erzar

Firm: STS - Minneapolis

I hereby certify that the above information is true and correct to the best of my knowledge.

Signature: \_\_\_\_\_

Print Initials: \_\_\_\_\_

Firm: \_\_\_\_\_

NOTE: Shaded areas are for DNR use only. See instructions for more information including a list of county codes.

Route to: Solid Waste ☐ Haz. Waste ☐ Wastewater ☐  
Env. Response & Repair ☐ Underground Tanks ☐ Other ☐

Facility/Project Name <u>Spickler LF</u>	County Name	Well Name <u>S-3AR</u>
Facility License, Permit or Monitoring Number	County Code	WIS. Unique Well Number DNR Well Number

1. Can this well be purged dry? ☐ Yes ☒ No

2. Well development method

- ☒ 41 surged with bailer and bailed  
☐ 61 surged with bailer and pumped  
☐ 42 surged with block and bailed  
☐ 62 surged with block and pumped  
☐ 70 surged with block, bailed and pumped  
☐ 20 compressed air  
☐ 10 bailed only  
☐ 51 pumped only  
☐ 50 pumped slowly  
☐ Other

3. Time spent developing well 110 min.

4. Depth of well (from top of well casing) 32.7 ft.

5. Inside diameter of well 2.06 in.

6. Volume of water in filter pack and well casing 4.9 gal.

7. Volume of water removed from well 50.0 gal.

8. Volume of water added (if any) 0.0 gal.

9. Source of water added N/A

10. Analysis performed on water added? ☒ Yes ☐ No  
(If yes, attach results)

16. Additional comments on development:

11. Depth to Water (from top of well casing)  
Before Development 16.62 ft.  
After Development 16.70 ft.

Date  
b. 03/21/96  
m m d d y y

Time  
c. 8:00 a.m.  
p.m.

12. Sediment in well bottom  
Before Development 8.0 inches  
After Development 0.0 inches

13. Water clarity  
Clear ☐ 10  
Turbid ☒ 15  
(Describe)

Fill in if drilling fluids were used and well is at solid waste facility:

14. Total suspended solids  
Before Development 878.0 mg/l  
After Development 1348.0 mg/l

15. COD  
Before Development 19.4 mg/l  
After Development 21.0 mg/l

Well developed by: Person's Name and Firm

Name: Gene Erzar

Firm: STS - Minneapolis

I hereby certify that the above information is true and correct to the best of my knowledge.

Signature: \_\_\_\_\_

Print Initials: \_\_\_\_\_

Firm: \_\_\_\_\_

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: FB03  
Previous Well Sampled: \_\_\_\_\_

Job No.: 843-84374XA  
Tester: DM  
Date Sampled: 3/21/96

## **GENERAL CONDITIONS:**

Surface Seal: OK N/A Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced? \_\_\_\_\_  
Temperature: 30 Clear/Cloudy/Rain

## **WELL DATA:**

Measuring Device: N/A  
Stick Up or Down: \_\_\_\_\_ (from Ground Surface)  
Depth to Water: \_\_\_\_\_ (from TPVC)  
Depth to Bottom: \_\_\_\_\_ (from TPVC)  
Length of Water: \_\_\_\_\_  
Free Product Observed: yes/no Thickness: \_\_\_\_\_ (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: N/A  
4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: \_\_\_\_\_ Sampling Device: \_\_\_\_\_  
Volume Required: \_\_\_\_\_  
Volume Purged: \_\_\_\_\_ Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: \_\_\_\_\_ Time Ended: \_\_\_\_\_  
Total Time Spent Purging: \_\_\_\_\_

Decon Method: Cleaned in office/Field Decon Method: \_\_\_\_\_

## **IN-SITU TESTING:**

Turbidity: clear turbid opaque  
Odor: none  
Color: clear  
pH: 7.78 @ 2.6 °C  
Uncorrected Conductivity: 2 x 1  
Water Temp. (from Cond.) 3.6  
Comments \_\_\_\_\_

Samples Collected		Preservatives
	#/Size	
VOCs-	<u>3-40 ml</u>	<u>Hal</u>
Metals-	<u>1-l</u>	<u>HNO3</u>
Indicator Parameters		<u>NONE 2-l</u>
Indicator Parameters		<u>1-l nat</u>

4 corrected Cond

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: SIAR  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374XA  
Tester: DLm  
Date Sampled: 3/21/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced?  
Temperature: 30 Clear Cloudy/Rain

## **WELL DATA:**

Measuring Device: MScope  
Stick Up or Down: + 3.0 (from Ground Surface)  
Depth to Water: 37.54 (from TPVC)  
Depth to Bottom: 41.79 (from TPVC)  
Length of Water: \_\_\_\_\_  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable Bailer  
Volume Required: \_\_\_\_\_  
Volume Purged: 3.0 gallons Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 15:30 Time Ended: 16:20  
Total Time Spent Purging: 50 min

Decon Method: \_\_\_\_\_ Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: <u>clear</u> turbid opaque	Samples Collected	Preservatives
Odor: <u>organic</u>	VOCs- <u>3-40 ml</u>	<u>Hcl</u>
Color: <u>light gray</u>	Metals- <u>1-e</u>	<u>HNO3</u>
pH: <u>6.62 @ 7.5</u> °C	Indicator Parameters	<u>NONE 2-e</u>
Uncorrected Conductivity: <u>211</u> x 10	Indicator Parameters	<u>1-e not</u>
Water Temp. (from Cond.) <u>7.5</u>		
Comments _____		
	<u>3246 umhos/cm</u>	

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: S1A + ns/msd  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374 x A  
Tester: DM  
Date Sampled: 3/21/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced?  
Temperature: 30 Clear Cloudy/Rain

## **WELL DATA:**

Measuring Device: mscope  
Stick Up or Down: -1.40 (from Ground Surface)  
Depth to Water: DM 34.25 (from TPVC)  
Depth to Bottom: 49.25 (from TPVC)  
Length of Water: 15  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disp Bailer Sampling Device: Disp Bailer  
Volume Required: 20  
Volume Purged: 20 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 15:10 Time Ended: 15:40  
Total Time Spent Purging: 30 min

Decon Method: \_\_\_\_\_ Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: <u>clear</u> turbid _____ opaque _____	Samples Collected	Preservatives
Odor: <u>none</u>	#/Size	<u>Hel</u>
Color: <u>clear</u>	VOCs- <u>9-40 ml</u>	<u>HNO<sub>2</sub></u>
pH: <u>6.65 @ 7.4</u> °C	Metals- <u>2-2</u>	<u>NONE 4-2</u>
Uncorrected Conductivity: <u>81</u> x 10	Indicator Parameters	<u>2-2</u>
Water Temp. (from Cond.) <u>7.3</u>	Indicator Parameters	
Comments <u>1254 Corrected Cond</u>		



# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: S-1  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374XA  
Tester: Dcm  
Date Sampled: 3/21/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced?  
Temperature: 30 Clear/Cloudy/Rain

## **WELL DATA:**

Measuring Device: m Scope  
Stick Up or Down: -30 (from Ground Surface)  
Depth to Water: 17.20 (from TPVC)  
Depth to Bottom: 21.05 (from TPVC)  
Length of Water: 3.85  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.08] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.08] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: 12  
Volume Purged: 1.0 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 15:00 Time Ended: 15:10  
Total Time Spent Purging: 10 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: clear turbid opaque  
Odor: none  
Color: clear  
pH: 6.72 @ 6.0 °C  
Uncorrected Conductivity: 191 x 1  
Water Temp. (from Cond.) 6.1  
Comments \_\_\_\_\_

Samples Collected  
VOCs- 3-40 mc #/Size  
Metals- \_\_\_\_\_  
Indicator Parameters NONE  
Indicator Parameters \_\_\_\_\_

Preservatives  
Hel

307 unhol/cm corrected cond

VOCs only

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: 52  
Previous Well Sampled: \_\_\_\_\_

Job No.: 843482X  
Tester: Dcm  
Date Sampled: 3/21/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced?  
Temperature: 30 Clear/Cloudy/Rain

## **WELL DATA:**

Measuring Device: mScope  
Stick Up or Down: -1.40 (from Ground Surface)  
Depth to Water: 5.76 (from TPVC)  
Depth to Bottom: 12.05 (from TPVC)  
Length of Water: 6.29  
Free Product Observed: yes no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: 13 gallons  
Volume Purged: 13 gallons Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 12:30 Time Ended: 13:00  
Total Time Spent Purging: 30 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: clear <u>turbid</u> opaque	Samples Collected	Preservatives
Odor: <u>none</u>	#/Size	
Color: <u>Brown/Tan</u>	VOCs- <u>3-40 ml</u>	<u>HCl</u>
pH: <u>7.07 @ 5.6</u> °C	Metals- <u>1-L</u>	<u>HNO3</u>
Uncorrected Conductivity: <u>230 x 1</u>	Indicator Parameters	<u>NONE 2-L</u>
Water Temp. (from Cond.) <u>5.8</u>	Indicator Parameters	<u>1-L NaOH</u>
Comments: <u>Corrected cond 373</u>		

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: S-2A  
Previous Well Sampled: \_\_\_\_\_

Job No.: 843747A  
Tester: Jim  
Date Sampled: 3/21/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Damaged  
Protector Pipe: OK Damaged  
Well Cap: OK Damaged  
Temperature: 30

Missing: \_\_\_\_\_  
Missing: \_\_\_\_\_  
Missing: If Missing Replaced?  
Clear Cloudy/Rain

## **WELL DATA:**

Measuring Device: m Scope  
Stick Up or Down: -1.40 (from Ground Surface)  
Depth to Water: 16.14 (from TPVC)  
Depth to Bottom: 23.59 (from TPVC)  
Length of Water: 7.45  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.08] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.08] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: 1.5 gallons  
Volume Purged: 20 gallons Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes/no

Purging - Time Start: 12:30 Time Ended: 12:45  
Total Time Spent Purging: 15 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: clear turbid opaque  
Odor: none  
Color: Brown/Tan  
pH: 6.63 @ 8.3 °C  
Uncorrected Conductivity: 292 x 1  
Water Temp. (from Cond.) 8.3  
Comments: \_\_\_\_\_

Samples Collected		Preservatives
	#/Size	
VOCs-	<u>3-40 m</u>	<u>Me1</u>
Metals-	<u>1-e</u>	<u>1-HNO3</u>
Indicator Parameters	<u>NONE</u>	<u>2-e</u>
Indicator Parameters	<u>1-e</u>	<u>no H</u>

corrected cond 438

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: S-2AR  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374XA  
Tester: Dem  
Date Sampled: 3/21/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced?  
Temperature: 30 Clear Cloudy/Rain

## **WELL DATA:**

Measuring Device: m Scope  
Stick Up or Down: 3.0 (from Ground Surface)  
Depth to Water: 18.99 (from TPVC)  
Depth to Bottom: 30.80 (from TPVC)  
Length of Water: 11.81  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: 23  
Volume Purged: 23 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 12:00 Time Ended: 12:30  
Total Time Spent Purging: 30 min

Decon Method: \_\_\_\_\_ Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: clear <u>turbid</u> opaque	Samples Collected	Preservatives
Odor: <u>none</u>	#/Size	HCl
Color: <u>light Tan / Brown</u>	VOCs- <u>3-40 ml</u>	HNO3
pH: <u>6.86 @ 6.6</u> °C	Metals- <u>1-2</u>	NONH2- <u>2</u>
Uncorrected Conductivity: <u>251 x 1</u>	Indicator Parameters	Indicator Parameters
Water Temp. (from Cond.) <u>7.0</u>		<u>1-2 no</u>
Comments	<u>Corrected cond 392 umhos/cm</u>	

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: S-3  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374 HA  
Tester: Dum  
Date Sampled: 3/21/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced?  
Temperature: 30 Clear Cloudy/Rain

## **WELL DATA:**

Measuring Device: in scope  
Stick Up or Down: N/A (from Ground Surface)  
Depth to Water: 15.78 (from TPVC)  
Depth to Bottom: 20.32 (from TPVC)  
Length of Water: 4.54  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.08] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.08] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: 10 gallons  
Volume Purged: 3 gallons Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: 9:05 Time Ended: 9:10  
Total Time Spent Purging: 5 min

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: <u>clear</u> turbid opaque	Samples Collected	Preservatives
Odor: <u>none</u>	VOCs- <u>3-40 ml</u>	<u>Hcl</u>
Color: <u>clear</u>	Metals- <u>1-l</u>	<u>HNO3</u>
pH: <u>6.09 @ 6.0</u> °C	Indicator Parameters	<u>NONE 2-l</u>
Uncorrected Conductivity: <u>229 x 1</u>	Indicator Parameters	<u>1-l NaOH</u>
Water Temp. (from Cond.) <u>6.1</u>		
Comments		

368 umhos/cm corrected cond

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler LF  
Location: Spencer  
Well Number: S-3A + Dupe  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374XA  
Tester: DLm  
Date Sampled: 3/21/96

## **GENERAL CONDITIONS:**

Snow cover limited inspection

Surface Seal: ☒ OK Damaged Missing: \_\_\_\_\_  
Protector Pipe: ☒ OK Damaged Missing: \_\_\_\_\_  
Well Cap: ☒ OK Damaged Missing: If Missing Replaced?  
Temperature: 30 ☒ Clear ☐ Cloudy/Rain

## **WELL DATA:**

Measuring Device: mScope  
Stick Up or Down: N/A (from Ground Surface)  
Depth to Water: 17.80 (from TPVC)  
Depth to Bottom: 33.90 (from TPVC)  
Length of Water: 16.10  
Free Product Observed: yes ☒ no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Bailer Sampling Device: Disposable  
Volume Required: 30  
Volume Purged: 30 Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes ☒ no

Purging - Time Start: 8:17 Time Ended: 8:54  
Total Time Spent Purging: 38

Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: <input checked="" type="radio"/> clear	turbid	opaque	Samples Collected	Preservatives
Odor: <u>none</u>			VOCs- <u>3-40 ml</u>	<u>Hcl</u>
Color: <u>clear</u>			Metals- <u>1-l</u>	<u>HNO3</u>
pH: <u>5.53</u> @ <u>8.4</u>			Indicator Parameters	<u>NONE 2-l</u>
Uncorrected Conductivity: <u>339 x 1</u>			Indicator Parameters	<u>1-l NaOH</u>
Water Temp. (from Cond.) <u>8.0</u>				
Comments: <u>corrected cond 339 umhos/cm</u>				

# SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: S-3AR  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374 XA  
Tester: DLM  
Date Sampled: 3/21/96

## GENERAL CONDITIONS:

Surface Seal: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced?  
Temperature: 30 Clear Cloudy/Rain

## WELL DATA:

Measuring Device: mscope  
Stick Up or Down: \_\_\_\_\_ (from Ground Surface)  
Depth to Water: \_\_\_\_\_ (from TPVC)  
Depth to Bottom: \_\_\_\_\_ (from TPVC)  
Length of Water: \_\_\_\_\_  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## PURGING/SAMPLING:

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.08] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.08] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: \_\_\_\_\_  
Volume Purged: \_\_\_\_\_ Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no

Purging - Time Start: \_\_\_\_\_ Time Ended: \_\_\_\_\_  
Total Time Spent Purging: \_\_\_\_\_

Decon Method: Cleaned in office/Field Decon Method: Disposable

## IN-SITU TESTING:

Turbidity: <u>clear</u> <u>turbid</u> opaque	Samples Collected	Preservatives
Odor: <u>none</u>	#/Size	
Color: <u>Brown</u>	VOCs- <u>3-40 ml</u>	<u>H<sub>2</sub>O</u>
pH: <u>6.10 @ 6.3</u> °C	Metals- <u>1-2</u>	<u>HNO<sub>3</sub></u>
Uncorrected Conductivity: <u>279 x 1</u>	Indicator Parameters	<u>NONE 2-2</u>
Water Temp. (from Cond.) <u>6.1</u>	Indicator Parameters	<u>1-2 260</u>
Comments: <u>449 umhos/cm corrected cond</u>		

# SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: 2A2  
Previous Well Sampled: \_\_\_\_\_

Job No.: 84374xA  
Tester: Dm  
Date Sampled: 3/22/96

## GENERAL CONDITIONS:

Surface Seal: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced?  
Temperature: 40 Clear Cloudy/Rain

## WELL DATA:

Measuring Device: m Scope  
Stick Up or Down: +2.6 (from Ground Surface)  
Depth to Water: 18.95 (from TPVC)  
Depth to Bottom: 31.00 (from TPVC)  
Length of Water: 12.05  
Free Product Observed: yes/no Thickness: N/A (in bailer/by I-Probe)

## PURGING/SAMPLING:

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Bailer Sampling Device: Bailer  
Volume Required: 16  
Volume Purged: 45  
Could Well Bail Dry? yes no Water Level After: \_\_\_\_\_

Purging - Time Start: 8:00 AM Time Ended: 10:00 AM  
Total Time Spent Purging: 2 hrs

Decon Method: \_\_\_\_\_ Cleaned in office/Field Decon Method: Disposable

## IN-SITU TESTING:

Turbidity: clear turbid \_\_\_\_\_ opaque \_\_\_\_\_

Odor: none

Color: clear

pH: 5.83 @ 8.3 °C

Uncorrected Conductivity: 199 x 1

Water Temp. (from Cond.) 8.1

Comments \_\_\_\_\_

## Samples Collected

VOCs- 3-40 ml #/Size \_\_\_\_\_ Preservatives He1

Metals- 1-2 \_\_\_\_\_ Preservatives He2

Indicator Parameters NONE 2-2

Indicator Parameters 1-2 nae

Corrected Cond 30 umhos/cm



# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spencer  
Well Number: S2  
Previous Well Sampled: \_\_\_\_\_

Job No.: 843742A  
Tester: Dum  
Date Sampled: 3/22/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced?  
Temperature: 40 Clear Cloudy/Rain

## **WELL DATA:**

Measuring Device: mscope  
Stick Up or Down: -40 (from Ground Surface)  
Depth to Water: \_\_\_\_\_ (from TPVC)  
Depth to Bottom: \_\_\_\_\_ (from TPVC)  
Length of Water: \_\_\_\_\_  
Free Product Observed: yes no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Disposable Sampling Device: Disposable  
Volume Required: \_\_\_\_\_  
Volume Purged: \_\_\_\_\_ Water Level After: \_\_\_\_\_  
Could Well Bail Dry? yes no Bails Dry  
Purging - Time Start: 9:00 Am Time Ended: 11:30  
Total Time Spent Purging: 2.5 hr  
Decon Method: Cleaned in office/Field Decon Method: Disposable

## **IN-SITU TESTING:**

Turbidity: <u>clear</u> turbid opaque	Samples Collected	Preservatives
Odor: <u>leachate?</u> organic	VOCs- <u>3-40 ml</u>	<u>MLL</u>
Color: <u>light Gray</u>	Metals- <u>1-c</u>	<u>HNO3</u>
pH: <u>@</u> °C	Indicator Parameters	<u>NONE 2-c</u>
Uncorrected Conductivity: <u>229 x 1</u>	Indicator Parameters	<u>1-c not H</u>
Water Temp. (from Cond.) <u>6.1</u>		
Comments _____		

36.8 corrected conc

# **SPICKLER LANDFILL SITE OBSERVATION WELL SAMPLING SHEET**

Fill out the entire form.  
If it does not apply  
mark N/A

Project Name: Spickler  
Location: Spina  
Well Number: S-2A  
Previous Well Sampled: \_\_\_\_\_

Job No.: 843742A  
Tester: Dm  
Date Sampled: 3/22/96

## **GENERAL CONDITIONS:**

Surface Seal: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Protector Pipe: OK Damaged \_\_\_\_\_ Missing: \_\_\_\_\_  
Well Cap: OK Damaged \_\_\_\_\_ Missing: If Missing Replaced?  
Temperature: 30-40 Clear/Cloudy/Rain

## **WELL DATA:**

Measuring Device: M Scope  
Stick Up or Down: - .40 (from Ground Surface)  
Depth to Water: \_\_\_\_\_ (from TPVC)  
Depth to Bottom: \_\_\_\_\_ (from TPVC)  
Length of Water: \_\_\_\_\_  
Free Product Observed: yes no Thickness: N/A (in bailer/by I-Probe)

## **PURGING/SAMPLING:**

Well Purging Calculations: 4 Well Volumes: [(length of water X 0.12)+0.06] X 29.9 For 2" well  
10 Well Volumes: [(length of water X 0.12)+0.06] X 74.8 For 2" well

Purging Device: Bailer/pump Sampling Device: Disp Bailer  
Volume Required: \_\_\_\_\_  
Volume Purged: 100 Bails / 100 pump Water Level After: \_\_\_\_\_  
Could Well Bailer Dry? yes no

Purging - Time Start: 8:55 A Time Ended: 15:30 p  
Total Time Spent Purging: \_\_\_\_\_

Decon Method: Cleaned in office/Field Decon Method: Disp Bailer

## **IN-SITU TESTING:**

Turbidity: clear <u>turbid</u> opaque	Samples Collected	Preservatives
Odor: <u>none</u>	#/Size	
Color: <u>Cloudy Grey</u>	VOCs- <u>3-40 ml</u>	<u>MEL</u>
pH: <u>5.90 @ 7.9</u> °C	Metals- <u>1-l</u>	<u>HNO3</u>
Uncorrected Conductivity: <u>281 x 1</u>	Indicator Parameters	<u>NONE 2-l</u>
Water Temp. (from Cond.) <u>8.0 28.1 Dm</u>	Indicator Parameters	<u>1-l</u>
Comments		<u>no H</u>

425 corrected conc

Route to: Solid Waste ☐ Haz. Waste ☐ Wastewater ☐  
Env. Response & Repair ☐ Underground Tanks ☐ Other ☐

Facility/Project Name <u>Spickie LF</u>	County Name	Well Name <u>S2AR</u>
Facility License, Permit or Monitoring Number	County Code	WIS Unique Well Number
		DNR Well Number

1. Can this well be purged dry? ☐ Yes ☒ No

2. Well development method

- surged with bailer and bailed ☒ 41  
 surged with bailer and pumped ☐ 61  
 surged with block and bailed ☐ 42  
 surged with block and pumped ☐ 62  
 surged with block, bailed and pumped ☐ 70  
 compressed air ☐ 20  
 bailed only ☐ 10  
 pumped only ☐ 51  
 pumped slowly ☐ 50  
 Other ☐

3. Time spent developing well 13.5 min.

4. Depth of well (from top of well casing) 31.0 ft.

5. Inside diameter of well 2.06 in.

6. Volume of water in filter pack and well casing 4.0 gal.

7. Volume of water removed from well 45.0 gal.

8. Volume of water added (if any) 0.0 gal.

9. Source of water added NIA

10. Analysis performed on water added? ☒ Yes ☐ No  
(If yes, attach results)

16. Additional comments on development: 2.6' Stickup

8:00 - 8:30 Surge! surge removed 15 gallons - Turbid  
 8:45 - 8:55 removed 10 gallons Turbid  
 9:20 - 9:30 removed 10 gallons. Becoming clear -  
 9:40 - 9:50 removed 10 gallons clear

	Before Development	After Development
11. Depth to Water (from top of well casing)	<u>18.95</u> ft.	<u>18.94</u> ft.
Date	<u>03/22/96</u> m m d d y y	<u>03/22/96</u> m m d d y y
Time	<u>7:45</u> <input type="checkbox"/> a.m. <input checked="" type="checkbox"/> p.m.	<u>10:00</u> <input type="checkbox"/> a.m. <input checked="" type="checkbox"/> p.m.
12. Sediment in well bottom	<u>0.0</u> inches	<u>0.0</u> inches
13. Water clarity	Clear <input type="checkbox"/> 10 Turbid <input checked="" type="checkbox"/> 15 (Describe) <u>Turbid</u>	Clear <input checked="" type="checkbox"/> 20 Turbid <input type="checkbox"/> 25 (Describe) <u>Clear</u>

Fill in if drilling fluids were used and well is at solid waste facility:

14. Total suspended solids 225.0 mg/l 33.0 mg/l  
 15. COD 19.1 mg/l 5.0 mg/l

Well developed by: Person's Name and Firm

Name: Dave Markelz

Firm: STS Consultants

I hereby certify that the above information is true and correct to the best of my knowledge.

Signature: \_\_\_\_\_

Print Initials: \_\_\_\_\_

Firm: \_\_\_\_\_

**STS GEO-ENVIRONMENTAL GROUP**  
**FIELD REPORT**



Job No. 84374xA

Project Spickler  
 Location Spencer WI  
 Client Weyohaus

Day Fri  
 Date 3/22/96  
 Weather 40- Clear

Mileage  
 Expenses

Arrive Job 7:30  
 Leave Job 5:30  
 Travel Time -

Total Chargeable Hours

10

Summary of Technical and/or Engineering Services performed, including field test data, locations, elevations & estimated depths.

Redeveloped wells S2AR, S2A & S2. Well S2AR was Surged & Purged with a PVC Bailer. An additional 45 gallons were removed and became clear. TSS & COD Samples collected before and After Development.

Well S2A was Surged & purged with a disposable PVC Bailer. 100 Gallons of water was removed but the water remained Silty and Tan in color. A whole pump and disposable Tubing was used to pump well 2A until clear. Pump rate of 1.0-1.5 gpm for Approx 1 hr.

Well S2 was purged dry several times prior to Sampling.

Collected Samples From: all Three wells. 3-40 mL HCl vials, 2-e amber no pres, 1-e NaOH were collected. Additional Sample was collected and Filtered in to a 1-e 1W HNO3.

Ph, Cond and Temp were measured and recorded on field Sampling sheet as in field log book. Observations of color odor & Turbidity were also recorded.

Samples Stored on Ice After collection.

Field Test Data is Estimated Pending Final Laboratory Results.

tgw/6/94/cpro gray ask

By:

D. M. Kozl.

STS Consultants, Ltd.

**STS GEO-ENVIRONMENTAL GROUP**  
**FIELD REPORT**



Project	Spickler LF	Job No.	84374XA
Location	Spencer WI	Day	SAT
Client	Weyer	Date	3/23/96
		Weather	30°S Cloudy
Mileage		Arrive Job	6:45
Expenses		Leave Job	12:30
		Travel Time	
		Total Chargeable Hours	5.75

Summary of Technical and/or Engineering Services performed, including field test data, locations, elevations & estimated depths.

Delivered Samples from Spickler LF, collected 3/22/96  
pm to HES in Madison.  
Returned to STS.

Field Test Data is Estimated Pending Final Laboratory Results.


mw6/94/opro gray ask

By:

D. Markel  
STS Consultants, Ltd.

STS

B



## **APPENDIX B**

### **Chain-of-Custody Forms**

# CHAIN OF CUSTODY RECORD

No 26856



Contact Person Jane Kettler  
 Phone No. (414) 359-3030 Office Milwaukee  
 Project No. 84374xA PO No. \_\_\_\_\_  
 Project Name Spickler LF

## Special Handling Request

- ☐ Rush  
☐ Verbal  
☐ Other

RECORD NUMBER 1 THROUGH 2

Laboratory Hazleton  
 Contact Person Matt Mares MS-R  
 Phone No. \_\_\_\_\_ WIR-1  
 Results Due STO Condition Cold Storage WIR-2  
 Acct. # 4892 Abbrev. STSO

Sample I.D.	Date	Time	Grab	Composite	No. of Containers	Sample Type (Water, soil, air, sludge, etc.)	Preservation		Field Data				Analysis Request	Smpl. Rec'd Composite or Sample (Include Major Contaminants)	Date Entered	LIMS #	MAR 14 1996	Init. LMD
							Y	N	PID/FID		PH	Special Cond.						
									Ambient	Sample								
D-mw205-0501	3/12	8:41	X		7	Water	X	X										
D-mw145-0501	3/12	9:40	X		7	Water	X	X										
D-mw155-0501	3/12	10:05	X		7	Water	X	X										
D-mw135-0501	3/12	11:35	X		7	Water	X	X										
D-mw135-0501	3/12	11:40	X		7	Water	X	X										
D-mw130-0501	3/12	12:00	X		7	Water	X	X										
D-mw150-0501	3/12	12:00	X		7	Water	X	X										
D-mw65-0501	3/12	15:22	X		7	Water	X	X										
D-mw190-0501	3/12	15:30	X		7	Water	X	X										

Collected by: <u>Dan &amp; McKel</u>	Date <u>3/12/96</u>	Time <u>Am/pm</u>	Delivery by: <u>Dunham</u>	Date <u>3/13/96</u>	Time <u>p.m.</u>
Received by:	Date	Time	Relinquished by:	Date	Time
Received by:	Date	Time	Relinquished by:	Date	Time
Received by:	Date	Time	Relinquished by:	Date	Time
Received for lab by: <u>Lynn Derry</u>	Date <u>3-14-96</u>	Time <u>855</u>	Relinquished by:	Date	Time

Laboratory Comments Only: Seals Intact Upon Receipt? ☐ Yes ☐ No ☐ N/A

Final Disposition: <u>Sample Time for 130 &amp; 150 is 12:00p</u>	Comments (Weather Conditions, Precautions, Hazards): <u>3-40 ml (H1), 1-e Filter w/ HNO<sub>3</sub>,</u> <u>2-e Amber, 1-e NaOH</u> <u>Reid with ice - LMD</u>
<u>For both (Sealed by two different Seals)</u>	



# CHAIN OF CUSTODY RECORD

No 26857



Contact Person Jane Kettler  
 Phone No. (414) 359-3030 Office Milwaukee  
 Project No. 84374XA PO No. \_\_\_\_\_  
 Project Name Spickler LI

## Special Handling Request

- ☐ Rush  
☐ Verbal  
☐ Other

RECORD NUMBER 2 THROUGH 2

Laboratory Matr marks  
 Contact Person Hazleton  
 Phone No. \_\_\_\_\_  
 Results Due STD

Sample I.D.	Date	Time	Grab	Composite	No. of Containers	Sample Type (Water, soil, air, sludge, etc.)	Preservation		Field Data				Analysis Request	Comments on Sample (Include Major Contaminants)
									PID/FID		PH	Special Cond.		
									Ambient	Sample				
							Y	N						
SLRD-MW195-0501	3/12	15:15	X		7	Water	X	X					low level Dm VOC, <del>AS</del> , AS, Ba, Cr, Mn, Fe, lead, mercury, Napthalene, phthalates, Cyanide	
SLRD-MW195-0599	3/12	15:20	X		7	Water	X	X						
SLRD-MWFB01-0504	3/12	16:00	X		7	Water	X	X						
SLRD-MWTB01-0501					3	Water							low level Dm VOC, <del>AS</del> , AS, Ba, Cr, Mn, Fe, lead, mercury, Napthalene, phthalates, Cyanide	

Collected by: <u>David Mcken</u>	Date <u>3/12/96</u>	Time _____	Delivery by: <u>Danham</u>	Date <u>3/13/96</u>	Time _____
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received for lab by: <u>Lynn Derry</u>	Date <u>3-14-96</u>	Time <u>855</u>	Relinquished by: _____	Date _____	Time _____

Laboratory Comments Only: Seals Intact Upon Receipt? ☐ Yes ☐ No ☐ N/A

Final Disposition: _____	Comments (Weather Conditions, Precautions, Hazards): <u>Rec'd with ice - LMO</u>
--------------------------	---

Distribution: Original and Green - Laboratory Yellow - As needed Pink - Transporter Goldenrod - STS Project File  
 Instructions to Laboratory: Forward completed original to STS with analytical results. Retain green copy.

9/94cp10k

STS Consultants Ltd.

# CHAIN OF CUSTODY RECORD

No 26906



Contact Person Jane Kettler  
 Phone No. (414) 359-3030 Office milwaukee  
 Project No. 84374 x A PO No. \_\_\_\_\_  
 Project Name Spickler

## Special Handling Request

- ☐ Rush  
☐ Verbal  
☐ Other

RECORD NUMBER 7 THROUGH 7

Laboratory Hazleton  
 Contact Person Matt Marks  
 Phone No. \_\_\_\_\_  
 Results Due STO

Sample I.D.	Date	Time	Grab	Composite	No. of Containers	Sample Type (Water, soil, air, sludge etc.)	Preservation		Field Data				Analysis Request	Comments on Sample (Include Major Contaminants)
							Y	N	PID/FID		PH	Special Cond.		
									Ambient	Sample				
SLRD-RW2543-0501	3/13	1:40	X		7	Water	X	X					Low level vocs, As, Ba, Cr, Mn, Fe lead, mercury, Naphthalene, phthalates, Cyanide	Condition <u>Gold</u> Storage <u>WIR-2</u> MSK Acct. # <u>4892</u> Abbrev. <u>STSO</u> <u>LMD</u> Smpl Recd <u>MAR 15 1996</u> <u>LMO</u> Date Entered <u>3-15-96</u> LIMS # <u>60300529</u> 546
SLRD-RW2543-0549	3/13	1:45	X		7	Water	X	X						
SLRD-RW2551-0501	3/13	2:05	X		17	Water	X	X						
SLRD-RWFB01-0501	3/13	2:15	X		7	Water	X	X						
SLRD-RWTB01-0501					2	Water								

Collected by: <u>David M. Kettler</u>	Date <u>3/13/96</u>	Time <u>pm</u>	Delivery by: <u>Punka</u>	Date <u>3/14/96</u>	Time <u>Am</u>
Received by:	Date	Time	Relinquished by:	Date	Time
Received by:	Date	Time	Relinquished by:	Date	Time
Received by:	Date	Time	Relinquished by:	Date	Time
Received for lab by: <u>Lyn Derry</u>	Date <u>3-15-96</u>	Time <u>9:15</u>	Relinquished by:	Date	Time

Laboratory Comments Only: Seals Intact Upon Receipt? ☐ Yes ☐ No ☐ N/A

Final Disposition: <u>RW 2551 MS/MSO</u>	Comments (Weather Conditions, Precautions, Hazards): <u>Rec'd with ice - LMD</u>

# CHAIN OF CUSTODY RECORD

Nº 26602



Contact Person Jane Kettler  
 Phone No. (414) 259-3030 Office Milwaukee  
 Project No. 84374XA PO No. \_\_\_\_\_  
 Project Name Spickler LF

## Special Handling Request

- ☐ Rush  
☐ Verbal  
☐ Other

RECORD NUMBER 1 THROUGH 1

Laboratory Hazleton  
 Contact Person McTi marks  
 Phone No. \_\_\_\_\_  
 Results Due STD

Sample I.D.	Date	Time	Grab	Composite	No. of Containers	Sample Type (Water, soil, air, sludge, etc.)	Preservation		Field Data				Analysis Request	Comments on Sample (Include Major Contaminants)
									PID/FID		PH	Special Cond.		
									Ambient	Sample				
							Y	N						
D-mw115-0501	3/13	8:47	X		7	Water	X	X					Low level voc's, AS, Ba, Mn, Fe, Lead, Mercury, Naphthalene, phthalates, Cyanide	
D-mw65-0501	3/13	10:03	X		7	Water	X	X						
D-mw75-0501	3/13	10:25	X		7	Water	X	X						
D-mw105-0501	3/13	9:55	X		17	Water	X	X						
D-mw70-0501	3/13	11:00	X		7	Water	X	X						
D-MWFB02-0501	3/13	12:00	X		7	Water	X	X						
D-mwTB02-0501					3	Water								
* Sample reads 60 - and 65 was read 3-14-96 - LMD														

Collected by: <u>David Markel</u>	Date <u>3/13/96</u>	Time _____	Delivery by: <u>Dunham</u>	Date <u>3/14/96</u>	Time <u>Am</u>
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received for lab by: <u>Lynn Derry</u>	Date <u>3-15-96</u>	Time <u>9:15</u>	Relinquished by: _____	Date _____	Time _____

Laboratory Comments Only: Seals Intact Upon Receipt? ☐ Yes ☐ No ☐ N/A

Final Disposition:	Comments (Weather Conditions, Precautions, Hazards):
<u>MW10 ms/ms Dupe</u>	<u>Rec'd with ice - LMD</u>

## CHAIN OF CUSTODY RECORD

№ 29426



Contact Person Jane Kettler  
 Phone No. (414) 359-3030 Office Milwaukee  
 Project No. 84374xA PO No. \_\_\_\_\_  
 Project Name Spickler LF

## Special Handling Request

- ☐ Rush  
☐ Verbal  
☐ Other

RECORD NUMBER 1 THROUGH 2

Laboratory HES  
 Contact Person Harley Cliff  
 Phone No. \_\_\_\_\_  
 Results Due 5/15 Condition Storage  
 Acct. # \_\_\_\_\_ Abbrev. \_\_\_\_\_

Sample I.D.	Date	Time	Grab	Composite	No. of Containers	Sample Type (Water, soil, air, sludge, etc.)	Preservation		Field Data				Analysis Request	Smp. Col. Rec'd (Include Major Contaminants)	Init.
							Y	N	PID/FID		PH	Special Cond.			
									Ambient	Sample					
<del>SLRD-S3A</del> - 0501	3/21	9:20	X		7	Water	X						Low level voc's, AS, Ba, Cr, Mn, Fe Lead, Mercury, Naphthalene, phthalates, Cyanide	MAR 28 1996 Condition Cold Storage WA-1 Acct. # 4872 Abbrev. STSO	GWS
SLRD-S3A-0599	3/21	9:25	X		7	Water	X								
SLRD-S3-0501	3/21	9:35	X		7	Water	X								
SLRD-S3AR-0503	3/21	9:55	X		7	Water	X	X						MAR 29 1996 Date Entered 3-25-96 LIMS # 6030076h	GWS
<del>SLRD-S3AR-0503</del>	<del>3/21</del>	<del>12:30</del>	<del>X</del>		<del>7</del>	<del>Water</del>	<del>X</del>	<del>X</del>							
<del>SLRD-S2-0501</del>	<del>3/21</del>	<del>13:05</del>	<del>X</del>		<del>7</del>	<del>Water</del>	<del>X</del>	<del>X</del>							
<del>SLRD-S2A-0501</del>	<del>3/21</del>	<del>16:48</del>	<del>X</del>		<del>7</del>	<del>Water</del>	<del>X</del>	<del>X</del>							
SLRD-S1A-0501	3/21	15:50	X		17	Water	X	X							
SLRD-S1AR-0503	3/21	16:25	X		7	Water	X	X							

Collected by: <u>David McKel</u>	Date <u>3/21/96</u>	Time <u>Am/pm</u>	Delivery by: <u>Dunham</u>	Date <u>3/22/96</u>	Time <u>Am</u>
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received for lab by: <u>H. Lina</u>	Date <u>3/23/96</u>	Time <u>10:10</u>	Relinquished by: _____	Date _____	Time _____

Laboratory Comments Only: Seals Intact Upon Receipt? ☐ Yes ☐ No ☐ N/A

Final Disposition:

Comments (Weather Conditions, Precautions, Hazards);

Res'd on ice - good condition  
Sample 53A-0599 - one bottle missing the A on label  
WLS

Distribution: Original and Green - Laboratory Yellow - As needed Pink - Transporter Goldenrod - STS Project File  
 Instructions to Laboratory: Forward completed original to STS with analytical results. Retain green copy.

9/94cp10k

STS Consultants Ltd.

# CHAIN OF CUSTODY RECORD

No. 00128



Contact Person Jane Kehr  
 Phone No. (414) 359-3030 Office Milwaukee  
 Project No. 84374 FA PO No. \_\_\_\_\_  
 Project Name Spickler

## Special Handling Request

- ☐ Rush  
☐ Verbal  
☐ Other

RECORD NUMBER 2 THROUGH 2

Laboratory HES  
 Contact Person Harly Cliff  
 Phone No. \_\_\_\_\_  
 Results Due STD

Sample I.D.	Date	Time	Grab	Composite	No. of Containers	Sample Type (Water, soil, air, sludge, etc.)	Preservation		Field Data				Analysis Request	Comments on Sample (Include Major Contaminants) Condition <u>Cold</u> Storage <u>W-1</u> Acct # <u>4892</u> Abbrev. <u>STSC</u> <u>W-1</u>	
							Y	N	PID/FID		PH	Special Cond.			
									Ambient	Sample					
SLRD-S3AR-0501	3/21	8:05			2	Water	X	X					TSS + CuD	Smp. Rec'd <b>MAR 23 1996</b> Init _____	
SLRD-S3AR-0502	3/21	9:50			2	Water	X	X							Date Entered <u>3-25-96</u>
<del>SLRD-S2AR-0501</del>	<del>3/21</del>	<del>10:35</del>			<del>2</del>	<del>Water</del>	<del>X</del>	<del>X</del>							LIMS # <u>60300766</u>
<del>SLRD-S2AR-0502</del>	<del>3/21</del>	<del>12:26</del>			<del>2</del>	<del>Water</del>	<del>X</del>	<del>X</del>							
SLRD-S1AR-0501	3/21	15:33			2	Water	X	X							
SLRD-S1AR-0502	3/21	16:23			2	Water	X	X							
SLRD-S1-0501	3/21	16:15			3	Water	X						low level VOC's only		
SLRD MWRBIS-0501					2	Water	X						" " "		

Collected by: <u>David Makler</u>	Date <u>3/21/96</u>	Time <u>Am/pm</u>	Delivery by: <u>Dunham</u>	Date <u>3/22/96</u>	Time <u>pm</u>
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received by: _____	Date _____	Time _____	Relinquished by: _____	Date _____	Time _____
Received for lab by: <u>William D. Smith</u>	Date <u>3/23/96</u>	Time <u>10:10</u>	Relinquished by: _____	Date _____	Time _____

Laboratory Comments Only: Seals Intact Upon Receipt? ☐ Yes ☐ No ☐ N/A

Final Disposition: _____	Comments (Weather Conditions, Precautions, Hazards): <u>Rec'd on Ice - Good condition</u> <u>Sample S1AR-0502 - one bottle labeled S2AR</u>
--------------------------	---

Distribution: Original and Green - Laboratory Yellow - As needed Pink - Transporter Goldenrod - STS Project File  
 Instructions to Laboratory: Forward completed original to STS with analytical results. Retain green copy.

9/94cp10k

STS Consultants Ltd.

# CHAIN OF CUSTODY RECORD

No 29429



Contact Person Jane Kettler  
 Phone No. (414) 359-3030 Office Milwaukee  
 Project No. 84374xA PO No. \_\_\_\_\_  
 Project Name Spickler LF

## Special Handling Request

- ☐ Rush  
☐ Verbal  
☐ Other

RECORD NUMBER 1 THROUGH 1

Laboratory NES  
 Contact Person Harley Cliff  
 Phone No. \_\_\_\_\_  
 Results Due STD Condition cold Storage GR-1

Sample I.D.	Date	Time	Grab	Composite	No. of Containers	Sample Type (Water, soil, air, sludge, etc.)	Preservation		Field Data				Analysis Request	Acct. # <u>4892</u> Abbrev. <u>STSO</u> Comments on Sample <u>146</u> (Include Major Contaminants) <u>MAR 23 1996</u> Date Entered <u>3-25-96</u> LIMS # <u>60300766</u>
							Y	N	PID/FID		PH	Special Cond.		
									Ambient	Sample				
<u>Development</u>														
<u>S2AR - Before</u>	<u>3/22</u>	<u>8:00</u>	<u>X</u>		<u>2</u>	<u>Water</u>	<u>X</u>	<u>X</u>					<u>TSS + COD</u>	
<u>S2AR - After</u>	<u>3/22</u>	<u>13:00</u>	<u>X</u>		<u>2</u>	<u>Water</u>	<u>X</u>	<u>X</u>					<u>TSS + COD</u>	
<u>S2AR - 0501</u>	<u>3/22</u>	<u>14:45</u>	<u>X</u>		<u>7</u>	<u>Water</u>	<u>X</u>	<u>X</u>					<u>low level VOCs, AS, Ba, CR, Mn, Fe</u>	
<u>S2 - 0501</u>	<u>3/22</u>	<u>15:10</u>	<u>X</u>		<u>7</u>	<u>Water</u>	<u>X</u>	<u>X</u>					<u>Lead Mercury, Naphthalene, phthalates,</u>	
<u>S2A - 0501</u>	<u>3/22</u>	<u>15:45</u>	<u>X</u>		<u>7</u>	<u>Water</u>							<u>Cyanide</u>	
<u>0 - MW FB03 0501</u>														

Collected by: <u>David Makers</u>	Date <u>3/22/96</u>	Time <u>PM</u>	Delivery by: <u>D. Makers</u>	Date <u>3/23/96</u>	Time <u>AM</u>
Received by:	Date	Time	Relinquished by:	Date	Time
Received by:	Date	Time	Relinquished by:	Date	Time
Received by:	Date	Time	Relinquished by:	Date	Time
Received for lab by: <u>Lynn Derry</u>	Date <u>3-23-96</u>	Time <u>1010A</u>	Relinquished by:	Date	Time

Laboratory Comments Only: Seals Intact Upon Receipt? ☐ Yes ☐ No ☐ N/A

Final Disposition:	Comments (Weather Conditions, Precautions, Hazards): <u>Rec'd with ice - LMD</u>


Distribution: Original and Green - Laboratory Yellow - As needed Pink - Transporter Goldenrod - STS Project File  
 Instructions to Laboratory: Forward completed original to STS with analytical results. Retain green copy.

9/94cp10k

STS Consultants Ltd.

STS

C



**APPENDIX C**

**HES Case Narrative**



May 6, 1996

Jane Kettler  
STS Consultants, LTD  
11425 West Lake Park Drive  
Milwaukee, WI 53224

Dear Ms. Kettler:

Enclosed are the data packages presenting the volatile organic analysis of 17 water samples plus QC, also included is the semivolatile and inorganic analysis of 14 water samples plus QC. Also enclosed are spreadsheets presenting the Chemical Oxygen Demand (COD) and Total Suspended Solids (TSS) results of six water samples. The samples were received on March 15 and 23, 1996 from the Spickler Landfill project. These Sample Delivery Groups (SDG) are designated as: SPK1Q2 and SPK1Q3.

LOW LEVEL VOLATILE ORGANIC ANALYSIS (Low Level 10/92 Contract)

- o Holding Times. All samples were analyzed within the holding time of ten days from sample receipt.
- o Method Blanks. The method blanks analyzed with the samples were within QC specifications.
- o GC/MS Tuning. The samples were run under BFB tunes which met all QC criteria.
- o Instrumental Calibrations. The initial and continuing calibrations were within QC criteria.
- o System Monitoring Compounds (SMCs). All surrogate recoveries were found to be within QC criteria.
- o Matrix Spike/Matrix Spike Duplicate. A matrix spike/matrix spike duplicate (MS/MSD) were analyzed for both SDGs. Sample MW10S0501 was designated as the parent sample in SDG SPK1Q2, while sample S1A0501 was designated as the parent sample in SDG SPK1Q3. The CLP SOW spiking compounds were added to the MS/MSDs. The recoveries ranged from 93% to 109% for SDG SPK1Q2, while the recoveries ranged from 101% to 161% for SDG SPK1Q3.

Ms. Kettler  
May 6, 1996  
Page 2

- o Laboratory Control Sample. The laboratory control samples (LCS) met all QC criteria with the following exceptions:

SDG SPK1Q2: The LCSs performed on 3/18/96, 3/28/96, and 3/29/96 had the compound vinyl chloride above the upper QC limit of 140% (158%, 146%, and 166%, respectively).

SDG SPK1Q3: The LCS performed on 3/29/96 had the compound vinyl chloride (166%) above the upper QC limit of 140%.

- o Internal Standard Recoveries. All internal standard recoveries were found to be within QC criteria with the following exceptions:

SDG SPK1Q3: The internal standard 1,4-dichlorobenzene-d4 fell below the lower QC limit for samples S1A0501DL, S1A0501MS, S1A0501MSD, and S1AR0503DL. The original analyses for the dilutions met QC criteria, but were being reanalyzed due to compounds exceeding the calibration range of the instrument.

- o Dilutions.

SDG SPK1Q2: Sample S30501 had total xylenes exceeding the calibration range of the instrument. This is denoted by the use of an 'E' flag on the Form 1. The sample was reanalyzed at a dilution. Both analyses are submitted in the data package.

SDG SPK1Q3: Samples S1A0501 and S1AR0503 each had compounds exceeding the calibration range of the instrument. This is denoted by the use of an 'E' flag on the Form 1. Each sample was reanalyzed at a dilution. Both analyses are submitted in each case.

- o Data Qualifiers. An 'X' flag was used on many Form 1s to denote that a manual quantitation was performed.

#### SEMIVOLATILE ORGANIC ANALYSIS

- o Holding Times. All samples were extracted and analyzed within the holding time specified in the CLP SOW, with the following exception:

SDG SPK1Q3: Sample MW13S-0599, from SDG SPK1Q1, required re-extraction due to noncompliant surrogates. The sample was re-extracted outside the holding time and is submitted with this SDG.

- o Method Blanks. The method blanks extracted and analyzed with the samples were within QC specifications.

Ms. Kettler  
May 6, 1996  
Page 3

- o GC/MS Tuning. The samples were run under DFTPP tunes which met all QC criteria.
- o Instrumental Calibrations. The initial and continuing calibrations were within QC criteria.
- o Surrogate Recoveries. All surrogate recoveries were found to be within QC criteria.
- o Matrix Spike/Matrix Spike Duplicate. A matrix spike/matrix spike duplicate (MS/MSD) were analyzed for both SDGs. Sample MW10S-0501 was designated as the parent sample for SDG SPK1Q2, while sample S1A-0501 was designated as the parent sample for SDG SPK1Q3. The compounds of concern were added to the MS/MSD. The recoveries ranged from 41% to 97% for SDG SPK1Q2, while the recoveries ranged from 83% to 165% for SDG SPK1Q3.
- o Internal Standard Recoveries. All internal standard recoveries were found to be within QC criteria.

#### INORGANIC ANALYSIS

- o Initial and Continuing Calibration Verification. All calibration verification standards were within QC specifications.
- o Method Blanks. All method blanks were within QC specifications.
- o ICP Interference Check. All ICP interference check samples were within QC specifications.
- o Spike Recovery. All matrix spike recoveries were within QC specifications.
- o Duplicate Analysis. All RPD values for the duplicate analysis were found to be within QC specifications.
- o Laboratory Control. All laboratory control results were within QC specifications.
- o Method of Standard Additions (MSA). The MSA was not required for these analyses.
- o ICP Serial Dilution. All percent differences (%D) for the serial dilution were within QC specifications with the following exception:


SDG SPK1Q3: The percent difference (%D) for iron (18.6%) exceeded the QC criteria. The Forms 1 and 9 are appropriately 'E' flagged. This represents the possibility of a matrix interference on the determination of this element.

o Analyses Comments.


SDG SPK1Q2: Two lead results were 'W' flagged, indicating that the post-digestion (analytical) spike was recovered outside the 85%-115% range, while the sample absorbance was less than 50% of the spike absorbance.

Please contact either Harley Cliff or Amy Austin if you have any questions regarding the data or require further assistance at (608) 232-3300.

Sincerely,



Amy L. Austin  
Supervisor  
Quality Assurance



Harley G. Cliff  
Supervisor  
Mass Spectrometry

cc: Central file  
Case file

April 24, 1996

Jane Kettler  
STS Consultants, LTD  
11425 West Lake Park Drive  
Milwaukee, WI 53224

Dear Ms. Kettler:

Enclosed are the data packages presenting the volatile organic analysis of 20 water samples plus QC, also included is the semivolatile and inorganic analysis of 18 water samples plus QC. The samples were received on March 14 and 15, 1996 from the Spickler Landfill project. This Sample Delivery Group (SDG) is designated as: SPK1Q1. The remaining results will be sent upon completion.

LOW LEVEL VOLATILE ORGANIC ANALYSIS (Low Level 10/92 Contract)

- o Holding Times. All samples were analyzed within the holding time of ten days from sample receipt.
- o Method Blanks. The method blanks analyzed with the samples were within QC specifications.
- o GC/MS Tuning. The samples were run under BFB tunes which met all QC criteria.
- o Instrumental Calibrations. The initial and continuing calibrations were within QC criteria.
- o System Monitoring Compounds (SMCs). All surrogate recoveries were found to be within QC criteria.
- o Matrix Spike/Matrix Spike Duplicate. A matrix spike/matrix spike duplicate (MS/MSD) were analyzed for sample RW2551-0501. The CLP SOW spiking compounds were added to the MS/MSD. The recoveries ranged from 96% to 146%.
- o Laboratory Control Sample. The laboratory control samples (LCS) met all QC criteria with the following exceptions:

Ms. Kettler  
April 24, 1996  
SDG SPK1Q1  
Page 2

The LCS performed on 3/15/96 and 3/18/96 had the compound vinyl chloride above the upper QC limit of 140% (152% and 158%, respectively).

- o Internal Standard Recoveries. All internal standard recoveries were found to be within QC criteria.
- o Dilutions. Samples MW13S0501 and MW13S0599 each had total xylenes exceeding the calibration range of the instrument. This is denoted by the use of an 'E' flag on the Form I. Each sample was reanalyzed at a dilution. Both analyses are submitted in each case.
- o Data Qualifiers. An 'X' flag was used on many Form Is to denote that a manual quantitation was performed.

#### SEMIVOLATILE ORGANIC ANALYSIS

- o Holding Times. All samples were extracted and analyzed within the holding time specified in the CLP SOW.
- o Method Blanks. The method blanks extracted and analyzed with the samples were within QC specifications.
- o GC/MS Tuning. The samples were run under DFTPP tunes which met all QC criteria.
- o Instrumental Calibrations. The initial and continuing calibrations were within QC criteria.
- o Surrogate Recoveries. All surrogate recoveries were found to be within QC criteria with the following exception:

Sample MW13S-0599 had all surrogate recoveries fall below their lower QC limits. The sample is in the process of being re-extracted. The re-extraction will be sent with the remainder of the data. Please see the attached Nonconformance /Corrective Action Report, #433.

- o Matrix Spike/Matrix Spike Duplicate. A matrix spike/matrix spike duplicate (MS/MSD) were analyzed for sample RW2551-0501. The compounds of concern were added to the MS/MSD. The recoveries ranged from 92% to 102%.
- o Internal Standard Recoveries. All internal standard recoveries were found to be within QC criteria.


Ms. Kettler  
April 24, 1996  
SDG SPK1Q1  
Page 3

INORGANIC ANALYSIS

- o Initial and Continuing Calibration Verification. All calibration verification standards were within QC specifications.
- o Method Blanks. All method blanks were within QC specifications.
- o ICP Interference Check. All ICP interference check samples were within QC specifications.
- o Spike Recovery. All matrix spike recoveries were within QC specifications.
- o Duplicate Analysis. All RPD values for the duplicate analysis were found to be within QC specifications.
- o Laboratory Control. All laboratory control results were within QC specifications.
- o Method of Standard Additions (MSA). The MSA was not required for these analyses.
- o ICP Serial Dilution. All percent differences (%D) for the serial dilution were within QC specifications.

Please contact either Harley Cliff or Amy Austin if you have any questions regarding the data or require further assistance at (608) 232-3300.

Sincerely,



Amy L. Austin  
Supervisor  
Quality Assurance

cc: Central file  
Case file  
Harley Cliff

Document # 438

HES, Inc.  
Nonconformance/Corrective Action Report

DIRECTIONS: Fill in the blanks and check appropriate boxes. Describe the nonconformance. For distribution, follow the flowchart in SOP OP-GEN.35.

1	Client: <u>STS</u>	Submitted By: <u>Jane Schneider</u>
	LIMS Number(s) affected: <u>6030490</u>	Assay Mnemonic: <u>HZWS</u>
		Date Of Occurrence: <u>4/12/96</u>
		Date Initiated: <u>4/19/96</u>

2	Describe Nonconformance (Problem):  <u>All surrogate recoveries outside QC limits low</u>
	Why Did the Problem Occur: <u>Not sure; chromatogram looks reasonably clean, so wouldn't think matrix interference (all internal stds fine).</u>
	Signature: <u>Philip Lind</u>

3	CORRECTIVE ACTION REQUIRED? <input type="checkbox"/> YES (fill out back of form) <input type="checkbox"/> NO
---	--

4	Supervisor Comments:  <u>Rechecked, reanalyze. Data will be included with a later SDG.</u>
	Signature: <u>H. Chy</u> Date: <u>4-22-96</u>

5	Project Manager Comments: (If Applicable) <input type="checkbox"/> Client Notified <input type="checkbox"/> (Date)
	Signature: _____ Date: _____



**Corrective Action**  
(Side 2)

Corrective action is required, complete this side of the form also. See other side for details of nonconformance.

STEP 1: Analyst/Supervisor: State what needs to be done to correct nonconformance and prevent reoccurrence.

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

**CORRECTIVE ACTION TAKEN**

Corrective Action will be (has been) completed on: \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

STEP 2: QA Manager Review. Date Received in QAU: 4/24/96

Corrective Action Acceptable ☒ Yes ☐ NO

QA Comments:

Reviewed by: Amy Austin

Date: 4/24/96

**QA FOLLOW-UP REPORT (If Applicable)**

QA Comments:

Signature: \_\_\_\_\_

Date: \_\_\_\_\_